

710

# SITE INVESTIGATION REPORT

## FORMER GALT GAS COMPANY SITE CAMBRIDGE, ONTARIO

OCTOBER 1991



Ontario

Environment  
Environnement



SITE INVESTIGATION REPORT  
FORMER GALT GAS COMPANY SITE  
CAMBRIDGE, ONTARIO

Report prepared for:

Waste Site Evaluation Unit  
Waste Management Branch  
Ontario Ministry of the Environment

Report prepared by:

Conestoga-Rovers & Associates Limited

NOVEMBER 1991



Cette publication technique  
n'est disponible qu'en anglais.

Copyright: Queen's Printer for Ontario, 1991  
This publication may be reproduced for non-commercial purposes  
with appropriate attribution.



### DISCLAIMER

This report was prepared for the Ontario Ministry of the Environment as part of a Ministry - Funded Project. The views and ideas expressed in this report are those of the author and do not necessarily reflect the views and policies of the Ministry of the Environment, nor does mention of trade names of commercial products constitute endorsement or recommendation for use.



## EXECUTIVE SUMMARY

The former Galt Gas Company Site is located within a parcel of property adjacent to the Grand River in Cambridge, Ontario. The current property owner purchased the property without knowing of the coal gasification plant which existed during the approximate period of 1886-1910. The property owner planned to re-develop the Site prior to being notified of the existence of the former coal gasification plant by the Ontario Ministry of the Environment (MOE).

The shoreline of the Grand River adjacent to the former coal gasification plant has apparently been extended outwards by filling. Currently, the Grand River Conservation Authority (GRCA) owns the property between the owner's property and the Grand River. A flood control berm is located on the GRCA property.

Several phases of investigation have been conducted. Initially, geotechnical boreholes were drilled for development purposes. These boreholes identified geologic conditions in the overburden. This work was not funded by the MOE. The investigative work conducted for the environmental investigation has included drilling 21 boreholes; chemical analysis of 16 soil samples; installation of four monitoring wells in the overburden; analysis of groundwater/fluid samples from three monitoring wells; inspection of the bottom of the Grand River adjacent to the former coal gasification plant; and analysis of water and sediment samples from the Grand River.

The geology of the Site from surface downwards includes a sand fill with gravel and rubble (up to 5 metres thick adjacent to the Grand River), an upper sequence of sands, a basal sand and gravel unit and bedrock. The bedrock is approximately 5 to 12 metres below ground surface. In some areas, thin silt layers are encountered within the overburden. A water table aquifer is found within the native sands at a depth of approximately 3.5 to 4.5 metres below ground surface. Water level measurements indicate that groundwater flow is in a southerly direction, parallel to that of the Grand River. The groundwater velocity was estimated to be approximately 1 metre/year.

The conclusions of this investigation are as follows:

- 1) The material underlying the former coal gasification plant includes concrete and soil containing coal tar residues. Gasoline and diesel fuel odours are also noted in this area.

- 2) Coal tar residues are present in soil to the west of the former coal gasification plant. These residues are found sporadically and may have been placed in part during historical filling along the edge of the Grand River.
- 3) Coal tar residues are present in soil beneath the GRCA flood control berm.
- 4) The coal tar residues are generally found in the saturated soils and represent a potential source of groundwater contamination.
- 5) Groundwater flow on the property appears to be approximately parallel to the Grand River and toward the south.
- 6) Groundwater at the southern end of the property does not exhibit contamination by PAHs. One monitoring well exhibits low concentrations of VOCs. The VOC contamination has various potential sources, including the coal tar residues and former automobile service stations in the area.
- 7) Coal tar residues have not migrated to the southern property boundary as evidenced by the absence of PAHs in soil and groundwater at the two monitoring wells at the boundary.
- 8) Coal tar residues are not visually present in the bed of the Grand River adjacent to the former coal gasification plant.
- 9) Water and sediment in the Grand River does not exhibit a detectable impact by PAHs from the former coal gasification plant.

The recommendations based on this investigation are as follows:

- 1) Any proposed disturbance of the area containing coal tar residues should be reported in writing to the MOE, Waste Management Branch prior to commencement and conducted in accordance with applicable regulations and guidelines.
- 2) A monitoring program should be implemented in the short term to assess the potential migration of contaminants in groundwater and surface water. This would include:
  - i) measuring water levels in the monitoring wells and the Grand River quarterly for one year;



- ii) collecting water samples from wells which do not contain coal tar and from two locations in the Grand River on a semi-annual basis for one year (groundwater samples would be analyzed for PAHs and VOCs, surface water samples would be analyzed for PAHs); and
- iii) reporting all results to MOE.

The need for monitoring would be re-assessed at the end of the one year period.

## TABLE OF CONTENTS

	<u>Page</u>
ACKNOWLEDGEMENT AND DISCLAIMER.....	i
EXECUTIVE SUMMARY.....	ii
1.0 INTRODUCTION.....	1
2.0 HISTORICAL LAND USE.....	3
2.1 OPERATION OF GAS WORKS (1886-1910).....	3
2.2 POST-CLOSURE OF GAS WORKS (1910-PRESENT) .....	4
3.0 FIELD INVESTIGATION.....	6
3.1 PHASE I AND II INVESTIGATIONS.....	7
3.2 PHASE III INVESTIGATION.....	7
3.3 PHASE IV INVESTIGATION.....	8
3.4 FIELD DATA SUMMARY.....	8
4.0 GEOLOGY/HYDROGEOLOGY.....	9
4.1 GEOLOGY.....	9
4.2 HYDROGEOLOGY.....	10
4.2.1 Groundwater Flow.....	11
4.2.2 Hydraulic Conductivity.....	11
4.2.3 Groundwater Flow Velocity.....	12
5.0 CONTAMINANT DISTRIBUTION.....	13
5.1 SOIL.....	13
5.1.1 Summary of Borehole Observations.....	13
5.1.2 Analytical Results of Soil Samples.....	15
5.2 GROUNDWATER.....	17
5.3 GRAND RIVER WATER AND SEDIMENT.....	18
6.0 CONCLUSIONS AND RECOMMENDATIONS.....	22
6.1 CONCLUSIONS.....	22
6.2 RECOMMENDATIONS.....	23

## LIST OF FIGURES

		<u>Following Page</u>
FIGURE 1.1	LOCATION OF MILL RACE ON THE GRAND PROPERTY	1
FIGURE 2.1	SITE OCCUPANCY - 1918	3
FIGURE 2.2	SITE OCCUPANCY - 1941	4
FIGURE 3.1	LOCATION OF BOREHOLES, MONITORING WELLS AND RIVER SAMPLING/INSPECTION	7
FIGURE 4.1	GEOLOGIC CROSS SECTION LOCATIONS	9
FIGURE 4.2	GEOLOGIC CROSS SECTION A-A'	9
FIGURE 4.3	GEOLOGIC CROSS SECTION B-B'	9
FIGURE 4.4	GEOLOGIC CROSS SECTION C-C'	9
FIGURE 4.5	GROUNDWATER CONTOURS	11
FIGURE 5.1	LOCATION OF BOREHOLES EXHIBITING CONTAMINATION	14

## LIST OF PLANS

PLAN 1	SITE PLAN	BACK POCKET
--------	-----------	-------------

## LIST OF TABLES

		<u>Following Page</u>
TABLE 4.1	SUMMARY OF WATER ELEVATION DATA	10
TABLE 5.1	SUMMARY OF ODOURS REPORTED IN GEOTECHNICAL SOIL BORINGS	13
TABLE 5.2	SUMMARY OF CONTAMINATION NOTED IN 1987 AND 1990 SOIL BORINGS	14
TABLE 5.3	PHASE I ANALYTICAL RESULTS - PAHs IN SOIL	15
TABLE 5.4	PHASE II ANALYTICAL RESULTS - PAHs IN SOIL LEACH	15
TABLE 5.5	PHASE II ANALYTICAL RESULTS - PAHs IN SOIL	15
TABLE 5.6	PHASE IV ANALYTICAL RESULTS - PAHs AND METALS IN SOIL	16
TABLE 5.7	ANALYTICAL RESULTS OF FLUID SAMPLE FROM OW8-87	17
TABLE 5.8	ANALYTICAL RESULTS OF GROUNDWATER SAMPLES	17
TABLE 5.9	ANALYTICAL RESULTS OF GRAND RIVER SEDIMENT SAMPLES	19
TABLE 5.10	ANALYTICAL RESULTS OF GRAND RIVER WATER SAMPLES	19

## LIST OF APPENDICES

APPENDIX A	GRAND RIVER INSPECTION REPORT BY INTEGRATED EXPLORATIONS
APPENDIX B	FIELD METHODS FOR PHASE IV INVESTIGATION
APPENDIX C	BOREHOLE LOGS
APPENDIX D	MISCELLANEOUS FIELD DATA
APPENDIX E	ANALYTICAL REPORTS




## 1.0 INTRODUCTION

Conestoga-Rovers & Associates (CRA) has completed an investigation of coal tar contamination at the site of the former Galt Gas Co. gas works in Cambridge, Ontario. The investigation has been carried out under the terms of a cost sharing agreement between the property owner (Mill Race on the Grand, Inc.) and the Ontario Ministry of the Environment (MOE) and a proposal by CRA dated June 1989 (1).

The initial phases of the investigation were reported by CRA in September 1987 (2). This report incorporates the information contained in the September 1987 report and provides an updated assessment of site conditions utilizing all data generated to date.

The area occupied by the former coal gasification plant is part of a larger parcel which was occupied by a textile mill until the mid 1980's. This parcel is herein referred to as the Mill Race on the Grand property (the property). The current owner purchased the property without knowing of the coal gasification plant which existed during the approximate period of 1886-1910.

Figure 1.1 shows the location of the Mill Race on the Grand property, which is situated on the west side of Water Street North in the City of Cambridge, north of the Parkhill Dam. The property fronts on Water Street and backs onto the flood control berm for the Grand River. The flood control berm property is owned by the Grand River Conservation Authority (GRCA).



SOURCE: TRI-CITY MAP (KITCHENER-WATERLOO-CAMBRIDGE),  
REGIONAL MUNICIPALITY OF WATERLOO  
PLANNING DEPARTMENT, 1985.

figure 1.1  
LOCATION OF MILL RACE  
ON THE GRAND PROPERTY



This report is organized as follows:

Section 2 contains a discussion of historical land use as originally reported in September 1987.

Section 3 contains a discussion of field investigation methods.

Section 4 contains a discussion of the geology/hydrogeology in the area investigated.

Section 5 contains a discussion of contaminant distribution in the various media examined.

Section 6 contains conclusions and recommendations.

## 2.0 HISTORICAL LAND USE


### 2.1 OPERATION OF GAS WORKS (1886-1910)

The history of the gasification plant and adjacent property was compiled through a review of documentation from the Cambridge Archives, the Cambridge Gallery and Library, the Gore-Mutual Insurance Company of Cambridge and oral communications with local residents.

The facilities present during operation of the former coal gasification plant are illustrated in Figure 2.1. This plan was reproduced from a fire insurance map stored at the Cambridge Gallery and Library. The fire insurance map was dated 1910 and was revised in 1918. Fire insurance maps are typically detailed site plans (to scale) of city blocks showing all building construction including materials. The original 1910 map depicted two large diameter gas holding tanks of 32,000 cubic foot and 15,000 cubic foot capacity respectively, separated by a large one-storey Purifying Retort building and several small storage buildings. The gas holding tanks measured approximately 2,400 square feet (55 feet diameter) and 1,600 square feet (45 feet diameter). The purifying-retort building measured approximately 2,500 square feet. The 1918 revised drawing does not record this layout. Figure 2.1 locates the above-mentioned tanks according to the 1910 survey. The Grand River shoreline configuration during the period was also recorded and is shown on Figure 2.1.

Based upon the above and the MOE release dated January 20, 1987 listing former coal gasification plant sites, the operations at

## RECORDED SHORELINE - 1918



LEGEND

GAS HOLDING TANK LOCATION  
AS PER 1910 FIRE INSURANCE  
MAP




figure 2.1  
SITE OCCUPANCY—1918


this plant started in the late 19th Century and ended prior to World War I (approximately 1886-1910).

Concurrent with coal gasification operations was the operation of the Galt Robe Company immediately to the north. The building consisted of one large three-storey structure. A lumber yard occupied the area to the south.

## 2.2 POST-CLOSURE OF GAS WORKS (1910-PRESENT)

Between 1910 and 1918, as indicated by the revised fire insurance map, the coal gasification operations had ceased and the structures were utilized for storage. In addition an auto garage and repair shop had located immediately adjacent to, and north of, the former coal gasification plant.

Figure 2.2 presents the property development/occupancy as defined on a 1941 Provincial Insurance Survey Map obtained from the Gore-Mutual Insurance Company, Cambridge. As indicated on Figure 2.2, the Grand River shoreline has been partially changed, presumably by filling, and the textile mill expanded over the former gas plant. The total frontage of the textile mill along Water Street was on the order of 520 feet as scaled from the 1941 plan. Measurements taken at the property during the investigative program confirm the frontage to be 530 feet indicating generally good agreement with the 1941 record. The construction history of the property remains relatively unchanged from 1941 until the present. Several



gasoline/service stations were apparently located along the east side of Water Street in recent years.

The textile mill was demolished to grade in the early 1980s. The basement floor slab and foundation walls still exist.

### 3.0 FIELD INVESTIGATION

Field investigations by CRA have been conducted in four phases and have consisted of the following:

- i) Drilling of 21 boreholes to determine geologic conditions and the presence of coal tar contamination.
- ii) Collection and chemical analysis of 16 soil samples from boreholes.
- iii) Installation of four monitoring wells to allow groundwater sample collection and for determining groundwater flow direction.
- iv) Collection and chemical analysis of groundwater/fluid samples from three monitoring wells.
- v) Inspection of the bottom of the Grand River adjacent to the former coal gasification plant.
- vi) Collection and analysis of water and sediment samples from the Grand River.

The first two phases of the field investigation included primarily borehole installation and were reported in September 1987(2). The third phase of the investigation included inspection of the Grand River and sampling of water and sediment from the river. This work was completed in early 1989. The fourth phase included installation of additional boreholes

and monitoring wells and additional sampling of water from the Grand River. This work was completed in the spring of 1990.


### 3.1 PHASE I AND II INVESTIGATIONS

The field investigation methods for Phase I and II are described in the September 1987 report (2). During Phase I and II, 13 boreholes were advanced using hollow stem or solid stem augers and one monitoring well was installed to monitor the presence of coal tar or groundwater contamination. Soil and groundwater samples were collected for analysis. Boreholes were drilled at the property prior to the coal tar investigation by Peto-MacCallum Ltd. This work was part of the geotechnical investigation for the proposed property re-development.

### 3.2 PHASE III INVESTIGATION

Phase III consisted of an underwater investigation of the Grand River bottom by Integrated Explorations Ltd. of Guelph, Ontario under the direction of CRA. The report of the investigation is contained in Appendix A. The river bottom was visually inspected and the sediments were "probed" over a 50 metres by 50 metres area adjacent to the former coal gasification plant as shown on Figure 3.1. Water and sediment samples were collected for analysis.







### 3.3 PHASE IV INVESTIGATION

The Phase IV investigation included the items described in the Proposal for Additional Investigative Work (1) (i.e. drilling of boreholes, installation of three monitoring wells and sampling of water in the Grand River). The work was conducted during the period of February to May 1990. The field methods for the Phase IV work are described in Appendix B.

### 3.4 FIELD DATA SUMMARY

Borehole logs for all borehole and well installations (including boreholes by Peto-MacCallum) are included in Appendix C. Additional field data which was collected (i.e. grain size data) are included in Appendix D. The locations of all boreholes, monitoring wells and river sampling points are shown on Figure 3.1 (presented previously).

Analytical reports for all samples collected during the entire program are contained in Appendix E.



## 4.0 GEOLOGY/HYDROGEOLOGY

### 4.1 GEOLOGY

Geologic cross-sections are used to illustrate geologic conditions. Cross-section locations are shown on Figure 4.1. The geological setting beneath the property, as shown on cross-section Figures 4.2, 4.3 and 4.4, is represented by fill overlaying an upper sequence of sands (SM, SP and SW) overlay a basal sand and gravel unit (SW-GP). A silt (ML) bed, of approximately 0.5 metre thickness, is found between these clastic units in the eastern area of the site as shown on Figure 4.2. An organic silt (OL) is noted to overlie the upper sands in the western areas of the site as shown on Figure 4.3. The soil classifications are from the modified Unified Soil Classification system and are defined in Appendix C.

The basal sand and gravel unit consists of a dense to very dense coarse sand and gravel with occasional cobbles. This unit is found approximately 4.0 to 8.0 metres below the surface and is inferred to be 2.0 to 5.0 metres thick, extending to the bedrock surface, approximately 5.0 to 12.0 metres below the surface.

The upper sands consist of a poorly to well graded, fine to coarse grained sand with occasional silt seams and traces of gravel. The sands are found approximately 1.5 to 5.0 metres below the ground surface and vary in thickness from 1.0 to 5.0 metres. The unit is continuous under the property but, terminates abruptly at the western property boundary as shown on Figure 4.4.













figure 4.2  
GEOLOGIC CROSS-SECTION A-A'  
SITE INVESTIGATION

SCALE (H) 1:1000  
(V) 1:100










figure 4.4  
GEOLOGIC CROSS-SECTION C-C'  
SITE INVESTIGATION

SCALE (H) 1:500  
SCALE (V) 1:100

LEGEND

GROUND SURFACE

WELL INSTALLATION

STRATIGRAPHIC DESCRIPTION

WATER ENCOUNTERED

STATIC WATER LEVEL (MAY 3, 1990)

MONITORING WELL SCREIN LOCATION



A silt or sandy silt bed of approximately 0.5 metres thickness is found stratigraphically between the upper sands and basal sand and gravel in the eastern portion of the property.

Loose, dark gray, organic silts with occasional sand seams are found in a limited area of the northwest quarter of the property as shown on Figure 4.2. These organic silts directly overly the upper sands and are approximately 2.0 metres in thickness.

The entire property is covered by a sand fill containing occasional gravel and limited amounts of construction rubble (brick pieces). This fill tends to increase in thickness from approximately 2.0 metres at the eastern property boundary, near Water Street, to approximately 5.0 metres at the western property boundary adjacent to the Grand River. It is believed that the shoreline of the Grand River was extended westward from Water Street by the placement of these fill materials.

## 4.2 HYDROGEOLOGY

A water table aquifer is found within the native sands at the property. The water table is approximately 3.5 to 4.5 metres below the ground surface or at an elevation ranging from 263.902 to 264.118 metres above mean sea level (AMSL). Table 4.1 summarizes the historical water level data.

TABLE 4.1

## SUMMARY OF WATER ELEVATION DATA

	Ref. Elev.	Water Elevation (m. AMSL)						
		4/29/87	2/27/90	3/14/90	3/26/90	5/3/90	5/22/90	12/11/90
Well Number								
OW8-87	269.178	264.548	264.298	264.718	264.438	264.118	264.498	264.418
OW14-90	268.409	--	264.049	264.459	264.299	263.909	264.279	264.249
OW15-90	268.542	--	264.052	264.502	264.272	263.902	264.312	264.232
OW17-90	269.560	--	264.210	264.540	264.380	264.035	264.360	264.330
River Station								
Number 1 (upstream)	265.715	--	--	--	264.824	264.815	--	--
Number 2 (downstream)	265.267	--	--	--	264.794	264.767	--	--



#### 4.2.1 Groundwater Flow

Groundwater flow within the water table aquifer is in a southerly direction, parallel to that of the Grand River as indicated by the water level data presented in Table 4.1, which were collected during spring and late fall conditions in 1990. This parallel groundwater flow pattern is thought to be significantly influenced by the Parkhill Dam immediately downstream of the property. During the period of water level measurements, the water elevation in the Grand River was found to be higher than the groundwater elevations on the property. This may be due to seasonal effects. Figure 4.5 illustrates the groundwater contours for May 3, 1990 taken from four groundwater observation wells: OW8-87, OW14-90, OW15-90 and OW17-90.

#### 4.2.2 Hydraulic Conductivity

The in situ hydraulic conductivity of the screened material of groundwater monitoring wells OW14-90 and OW15-90 was determined by single well response testing of the wells. Data from these tests are presented in Appendix D. The hydraulic conductivity of these wells, as calculated following Hvorslev (1951) (5) is  $1.0 \times 10^{-3}$  cm/sec and  $6.0 \times 10^{-5}$  cm/sec, respectively. The geometric mean of these values is  $2.4 \times 10^{-5}$  cm/sec and is used to characterize the hydraulic conductivity of the aquifer.





0 10 20 30m  
SCALE: 1:1000  
APPROXIMATE

# LEGEND

EXISTING GRADE

EXISTING SANITARY SEWER

EXISTING MANHOLE LOCATION

PETO-MCCALLUM BOREHOLE LOCATION

CRA BOREHOLE LOCATION

CRA MONITORING WELL LOCATION

GROUNDWATER ELEVATION  
IN METERS (AM SL.)

RIVER LEVEL  
STATION No. 1  
(264.815)

RIVER LEVEL  
STATION No. 2  
(264.767)

GRAND RIVER

WATER STREET

SIMCOE STREET




figure 4.5  
GROUNDWATER CONTOURS  
MAY 3, 1990



#### 4.2.3 Groundwater Flow Velocity

The average horizontal groundwater flow velocity can be determined using the modified Darcy equation:

$$\bar{V} = \frac{K i}{n}$$

where:

- K - hydraulic conductivity,
- i - horizontal hydraulic gradient, and
- n - effective porosity.

Using the geometric mean of the hydraulic conductivity of  $2.4 \times 10^{-6}$  m/sec ( $2.4 \times 10^{-4}$  cm/sec), a horizontal hydraulic gradient of 0.0036 (m/m) and an assumed effective porosity of 0.30, a horizontal linear groundwater velocity of  $2.9 \times 10^{-8}$  m/sec or 0.93 m/yr is calculated.

## 5.0 CONTAMINANT DISTRIBUTION

### 5.1 SOIL

#### 5.1.1 Summary of Borehole Observations

A total of 22 boreholes were completed by Peto-MacCallum Ltd. (Peto) for geotechnical investigation as discussed in the September 1987 report (2). Peto reported oil odours in several samples recovered during the investigation. Table 5.1 presents a summary of the location, depth and soil stratigraphy where the odours were reported.

The location of soil borings conducted by CRA in 1987 were selected on the basis of information from Peto borings, the location of the former coal gasification plant and the location of potential areas of contact with subsurface material during the proposed property development.

The soil borings conducted in 1990 by CRA were placed to define the extent of contamination outside of the limits of the former coal gasification plant and for installation of monitoring wells at the southern property boundary. In addition, a total of two boreholes and one monitoring well were to be placed through the top of the GRCA flood control berm. This part of the program was modified, in consultation with the MOE, because of difficulties and safety concerns regarding access of drilling equipment to the top of the berm. Two holes were drilled on the side of the berm (BH16-90, OW17-90) on GRCA property. One of these two boreholes (OW17-90) was completed as an observation well.

TABLE 5.1  
SUMMARY OF ODOURS  
REPORTED IN GEOTECHNICAL SOIL BORINGS

<i>Borehole</i>	<i>Depth ft (m) BGS</i>	<i>Geodetic Elev. ft (m) AMSL</i>	<i>Soil/Odour<sup>(1)</sup> Description</i>	<i>Remarks</i>
103	12.5 (3.81)	868 (264.56)	Sand and Silt Fill/ Strong oil smell	West of reported gas holder location
104	11 (3.35)	865 (263.66)	Coarse Sand/Strong smell of oil	Inside purifying retort building
202	10 (3.05)	870 (265.18)	Sand and Gravel Fill/Strong smell of oil	West of reported gas holder location
108	15 (4.57)	863 (263.05)	Fine to Medium Sand/ Strong smell of oil	Near north property limit

Note:

(1) As presented by Peto-MacCallum Ltd.

Table 5.2 contains a summary of the contamination noted in the soil borings conducted by CRA in 1987 and 1990. Figure 5.1 shows in plan view the locations where contamination was noted. From this information, the following general observations are made:

- i) Concrete material is present beneath the existing textile mill foundation where the former coal gasification plant was located.
- ii) Odours of coal tar, gasoline and diesel fuel are noted in the area of the former coal gasification plant.
- iii) The contamination is generally not encountered until the water table is reached.
- iv) The boreholes exhibiting the greatest amount of coal tar contamination are OW8-87, BH10-87 and BH13-87.
- v) A coal tar odour is noted at the north end of the property along with coal fragments.
- vi) Odours are noted in boreholes installed on GRCA property.
- vii) Contamination is not noted at boreholes on the southern property boundary (OW14-90, OW15-90).



TABLE 5.2

SUMMARY OF CONTAMINATION NOTED IN  
1987 AND 1990 SOIL BORINGS

<i>Borehole</i>	<i>Description</i>
BH1-87	- none
BH2-87	- strong coal tar odour at water table (El. 263.8 m)
BH3-87	- coal tar odour at water table (El. 264.8 m)
	- strong gasoline odour (El. 263.7 m)
BH4-87	- strong coal tar odour at water table (El. 264.6 m)
	- strong gasoline odour (El. 264.0 m)
BH5-87	- none
BH6-87	- strong coal tar odour beneath buried concrete slab (El. 264.6 m)
BH7-87	- coal tar odour (El. 267.0 m)
OW8-87	- strong coal tar odour and coal tar at water table (El. 264.8 m) down to and into fine grained layer (El. 262.0 m)
BH9-87	- slight coal tar odour above probable concrete (El. 266.0 m)
BH10-87	- diesel fuel odour at water table (El. 264.8 m)
	- strong coal tar odour and coal tar (El. 263.0 m)
BH11-87	- strong diesel fuel odour at water table (El. 264.8 m)
BH12-87	- strong diesel odour at water table (El. 265.0 m)
BH13-87	- slight coal tar odour at water table (El. 264.5 m) with increasing coal tar odour with depth
	- coal tar saturated above thin silt/sand layer (El. 262.2 m)
OW14-90	- none
OW15-90	- none
BH16-90	- very slight odour (El. 263.7 m)
	- slight odour, water discoloured (El. 262.3 m)
	- moderate odour in sand/gravel below silt layer (El. 261.0 m)
OW17-90	- slight odour in silt layer (El. 264.0 m)
	- slight odour in sand layer (El. 263.0 m)
BH18-90	- strong odour and sheen (El. 263.0 m)
	- strong odour and product (El. 262.0 m)
BH19-90	- none
BH20-90	- strong odour and product (El. 262.5 m)
BH21-90	- none







### 5.1.2 Analytical Results of Soil Samples

During Phase I, two soil samples were analyzed for the indicator polynuclear aromatic hydrocarbons (PAHs); naphthalene and benzo(a)pyrene. These compounds were selected as indicators because of mobility (naphthalene) and carcinogenicity (benzo(a)pyrene). The results are contained in Table 5.3. One sample was obtained from the vicinity of the former coal gasification plant (BH6-87) and the other was obtained from the north end of the property (BH7-87) where odours were noted from the geotechnical investigation. The only detection was naphthalene at BH6-87.

During Phase II, ten soil samples were analyzed for PAHs in leachate from soil and two soil samples were analyzed for total concentration of PAHs. These results are contained in Tables 5.4 and 5.5, respectively.

As shown in Table 5.4, benzo(a)pyrene was not detected in any of the leach samples. There were no detections of PAHs in the leach samples collected from the unsaturated zone. Various PAHs were detected in the leach samples collected from the saturated zone. The number of PAH compounds and their concentrations in the leach samples collected from within the silt layer at BH10-87 (4.6 - 5.2 m) are significantly lower than those of samples collected in the saturated zone above the silt layer at the same borehole.

With respect to the total PAH concentrations shown in Table 5.5, several PAHs including benzo(a)pyrene were detected in soil

TABLE 5.3  
PHASE I ANALYTICAL RESULTS  
PAHs IN SOIL

<i>Sample Location</i>	<i>Depth m (ft)</i>	<i>Concentration (ppm) (1)</i>	
		<i>Naphthalene</i>	<i>Benzo(a)pyrene</i>
BH6-87	2.4 (8)	2.38	<0.5
BH7-87	3.0-3.6 (10-12)	<0.05	<0.05

Notes:

1. Total concentration in soil

PHASE II ANALYTICAL RESULTS  
PAHs IN SOIL LEACH

PAH Compound ( $\mu\text{g/l}$ )	OW8-87		BH10-87				46-53.2 m (15.0-17.0 ft)	
	3.8-4.4 m (12.5-14.5 ft)	[5] MDL	1.5-2.1 m (5.0-7.0 ft)	[4] MDL	2.3-2.9 m (7.5-9.5 ft)	[5] MDL	3.8-4.4 m (12.5-14.5 ft)	[5] MDL
Acenaphthene	50.4	0.2	-	0.1	27.1	0.1	3.4	1
Acenaphthylene	2.7	0.2	-	0.1	0.4	0.1	355	1
Anthracene	0.5	0.2	-	0.1	1	0.1	21	1
Benz(a)Anthracene+Chrysene	-	0.2	-	0.1	-	0.1	-	1
Benzo(b)Fluoranthene and Benzo(k)Fluoranthene	-	0.2	-	0.1	-	0.1	-	2
Benzo(a)Pyrene	-	0.2	-	0.1	-	0.1	-	2
Benzo(g,h,i)Perylene	-	0.4	-	0.2	-	0.2	-	5
Dibenz(a,h)Anthracene	-	0.4	-	0.2	-	0.2	-	5
Fluoranthene	-	0.2	-	0.1	0.2	0.1	5.6	1
Fluorene	6.7	0.2	-	0.1	5.1	0.1	82	1
Indeno(1,2,3-cd)Pyrene	-	0.4	-	0.2	-	0.2	-	5
Naphthalene	240	0.2	-	0.1	0.3	0.1	777	1
Phenanthrene	6.6	0.2	-	0.1	6	0.1	160	1
Pyrene	-	0.2	-	0.1	0.5	0.1	6.1	1

TABLE 5.4

PHASE II ANALYTICAL RESULTS  
PAHs IN SOIL LEACH

PAH Compound ( $\mu\text{g/l}$ )	BH11-87			BH12-87			BH13-87		
	2.3-2.9 m (7.5-9.5 ft)	[5]	MDL	0.75-1.35 m (2.5-4.5 ft)	[4]	MDL	2.3-2.9 m (7.5-9.5 ft)	[5]	MDL
Acenaphthene	0.3		0.1	-		0.1	-		0.1
Acenaphthylene	-		0.1	-		0.1	-		0.1
Anthracene	-		0.1	-		0.1	-		0.1
Benz(a)Anthracene+Chrysene	-		0.1	-		0.1	-		0.1
Benzo(b)Fluoranthene and Benzo(k)Fluoranthene	-		0.1	-		0.1	-		0.1
Benzo(a)Pyrene	-		0.1	-		0.1	-		0.1
Benzo(g,h,i)Perylene	-		0.2	-		0.2	-		0.2
Dibenz(a,h)Anthracene	-		0.2	-		0.2	-		0.2
Fluoranthene	-		0.1	-		0.1	-		0.1
Fluorene	0.2		0.1	-		0.1	-		0.1
Indeno(1,2,3-cd)Pyrene	-		0.2	-		0.2	-		0.2
Naphthalene	1.6		0.1	-		0.1	-		0.1
Phenanthrene	0.4		0.1	-		0.1	0.2		0.1
Pyrene	-		0.1	-		0.1	-		0.1
							1.5-2.1 m (5.0-7.0 ft)	[4]	MDL
							5.3-5.9 m (17.5-19.5 ft)	[5]	MDL
									47.7
									283
									6.2
									-
									-
									3.5
									82
									-
									10,550
									117
									5.7

Notes:

- [1] MDL = Method Detection Limit
- [2] Blank value indicates compound not detected at the MDL
- [3] Total concentration in soil leach
- [4] Sample from unsaturated zone
- [5] Sample from saturated zone
- [6] Sample from within or below silt layer



TABLE 5.5  
PHASE II ANALYTICAL RESULTS  
PAHs IN SOIL

<i>PAH Compound (ppm)</i>	<i>BH13-87</i>		<i>OW8-87</i>	
	<i>5.3-5.9 m (17.5-19.5 ft)</i>	<i>MDL</i>	<i>3.8-4.4 m (12.5-14.5 ft)</i>	<i>MDL</i>
Acenaphthene	2,230	30	--	3
Acenaphthylene	160	30	89.2	3
Anthracene	1,250	30	55.8	3
Benz(a)Anthracene	400	30	11.3	3
Benzo(b)Fluoranthene and Benzo(k)Fluoranthene	420	50	TR	5
Benzo(a)Pyrene	530	50	TR	5
Benzo(g,h,i)Perylene	330	150	--	15
Chrysene	640	30	23.7	3
Dibenz(a,h)Anthracene	--	150	--	15
Fluoranthene	2,400	30	112	3
Fluorene	780	30	16.1	3
Indeno(1,2,3-cd)Pyrene	220	150	--	15
Naphthalene	10,300	30	180	3
Phenanthrene	5,250	30	188	3
Pyrene	510	30	24.8	3

Notes:

1. MDL = Method Detection Limit
2. Blank value indicates compound not detected at the MDL
3. TR = Trace
4. Total concentration in soil

samples. The concentrations present are higher in the vicinity of the former coal gasification plant (BH13-87) than at the property boundary (OW8-87). However, these samples were obtained from different depth horizons, and the concentrations of PAHs at a given location are expected to vary with depth due to the gravity effect on coal tar migration.

During Phase IV, two soil samples were collected and analyzed for PAHs and metals. These results are contained in Table 5.6. The samples were collected from the southern property boundary (OW14-90) and beneath the GRCA flood control berm (OW17-90). These samples were obtained from the saturated soil zone.

With respect to the PAH data, there were no detections at OW14-90 and there were several detections at OW17-90 at concentrations of approximately 1 ppm or less. The concentrations found at OW17-90 are significantly lower than those at OW8-87 which is approximately 30 metres upgradient of OW17-90 with respect to groundwater flow. This would be expected if the contaminants at OW17-90 were present as a result of transport with groundwater. With respect to the metals data, the concentrations present in both samples are similar to background concentrations of metals in surface soil in an urban location. The concentrations present are similar to or lower than the upper limits of normal concentrations in Ontario urban surface soil presented by the MOE (3).

TABLE 5.6

PHASE IV ANALYTICAL RESULTS  
PAHs AND METALS IN SOIL

<i>Parameter</i>	<i>Sample Location</i>	
	<i>OW14-90 (3.81 - 4.42m)</i>	<i>OW17-90 (5.33 - 5.94 m)</i>
<u>PAHs (ppm)</u>		
Acenaphthene	<0.05	0.69
Acenaphthylene	<0.05	0.05
Anthracene	<0.05	0.35
Benz(a)anthracene	<0.05	0.19
Benzo(b)fluoranthene		
and Benzo(k)fluoranthene	<0.12	0.24
Benzo(a)pyrene	<0.1	0.2
Benzo(g,h,i)perylene	<0.2	<0.2
Chrysene	<0.05	0.21
Fluoranthene	<0.05	0.53
Fluorene	<0.05	0.32
Indeno(1,2,3-cd)pyrene		
and Dibenz(a,h)anthracene	<0.25	<0.25
Naphthalene	<0.05	0.42
Phenanthrene	<0.05	1.2
Pyrene	<0.05	0.75
<u>Metals (ppm)</u>		
Hexavalent Chromium	0.179	0.28
Zinc	56	89/92
Cadmium	0.10	0.30/0.40
Cobalt	2.5	2.5/2.5
Copper	13.5	14.5/12.5
Lead	5.0	18.0/20.0
Chromium	17	23/24
Nickel	9	12/13
Beryllium	<1	<1/<2
Molybdenum	4	4/4
Vanadium	14	24/27
Barium	17	38/42
Mercury	<0.02	<0.02
Arsenic	<0.5	3.0/3
Selenium	<0.5	<0.5/<1
Silver	<0.5	<0.5/<1
Antimony	<1	<1/<2

## 5.2 GROUNDWATER

Monitoring wells OW8-87 and OW17-90 have been noted to contain non-aqueous phase liquids (e.g. oil, tar). A fluid sample was collected from OW8-87 and analyzed for PAHs as part of Phase II. This sample contained elevated concentrations of PAHs and VOCs but the sample is not indicative of groundwater quality. The analytical results for this sample are contained in Table 5.7. Monitoring well OW17-90 was not sampled since the well contains non-aqueous phase liquids which would interfere with the assessment of groundwater quality at this location.

As discussed in Section 4, groundwater flow at the property is towards the south. Monitoring wells OW14-90 and OW15-90 are expected to intercept floating and dissolved contaminants in groundwater which passes through the soil beneath the former coal gasification plant and vicinity.

The analytical results for groundwater samples collected in 1990 from OW14-90 and OW15-90 are contained in Table 5.8. PAHs were not detected in either sample. Volatile organic compounds (VOCs) were not detected in the sample from OW15-90. Several VOCs were detected in the sample from OW14-90 including chloroform, ethylbenzene and xylenes at concentrations of up to 4.3 µg/L. A total concentration of 16 µg/L of untargeted aromatic compounds was also detected. The VOCs which were detected in OW14-90 are not necessarily solely related to coal tar deposits, but may be related to petroleum products. An auto garage and some gasoline service stations are known to have existed in the area. These facilities would

TABLE 5.7

## ANALYTICAL RESULTS OF FLUID SAMPLE FROM OW8-87

<i>Compound</i>	<i>MDL</i>	<i>OW8-87</i>
<i>PAHs (µg/L)</i>		
Acenaphthene	10	112
Acenaphthylene	10	19.3
Anthracene	10	126
Benz(a)Anthracene	10	33.7
Chrysene	10	52.5
Benzo(b)Fluoranthene and Benzo(k)Fluoranthene	20	41
Benzo(a)Pyrene	20	54.6
Benzo(g,h,i)Perylene	50	TR
Dibenz(a,h)Anthracene	50	-
Fluoranthene	10	239
Fluorene	10	303
Indeno(1,2,3-cd)Pyrene	50	TR
Naphthalene	10	8,788
Phenanthrene	10	805
Pyrene	10	267

TABLE 5.7

## ANALYTICAL RESULTS OF FLUID SAMPLE FROM OW8-87

<i>Compound</i>	<i>MDL</i>	<i>OW8-87</i>
<i>VOCs (µg/L)</i>		
Benzene	1,000	8,940
Bromodichloromethane	100	-
Bromoform	500	-
Bromomethane	100	-
Carbon Tetrachloride	500	-
Chlorobenzene	100	-
Chloroethane	100	-
2-Chloroethyl Vinyl Ether	5,000	-
Chloroform	100	-
Chloromethane	100	-
Dibromochloromethane	100	-
1,2-Dichlorobenzene	150	-
1,3-Dichlorobenzene	150	-
1,4-Dichlorobenzene	150	-
1,1-Dichloroethylene	100	-
1,1-Dichloroethane	100	-
1,2-Dichloroethane	100	-
trans-1,2-Dichloroethylene	100	-
Dichloromethane	5,000	-
1,2-Dichloropropane	100	-
cis-1,3-Dichloropropene	250	-
trans-1,3-Dichloropropene	100	-
Ethylbenzene	50	5,000
A-Methylstyrene	50	130
Mesitylene	50	740
1,1,2,2-Tetrachloroethane	1,000	-
Tetrachloroethylene	100	-
Toluene	500	4,190
1,1,1-Trichloroethane	100	-
1,1,2-Trichloroethane	250	-
Trichloroethylene	100	-
Trichlorofluoromethane	500	-
m+p Xylene	50	1,410
o-Xylene	50	780
Vinyl Chloride	250	-
Other Aromatic Compounds	50	-

## Notes:

1. MDL = Method Detection Limit
2. Blank value indicates not detected at the MDL
3. Other Aromatic Compounds = Total concentration of tri- and tetramethylbenzenes using the response factor of mesitylene
4. TR = Trace

TABLE 5.8

## ANALYTICAL RESULTS OF GROUNDWATER SAMPLES

<i>Compound</i>	<i>MDL</i>	<i>OW14-90</i>	<i>OW15-90</i>
<i>PAHs (µg/L)</i>			
Acenaphthene	1	ND	ND
Acenaphthylene	1	ND	ND
Anthracene	1	ND	ND
Benzo(a)Anthracene	1	ND	ND
Benzo(b)Fluoranthene	1	ND	ND
Benzo(k)Fluoranthene	1	ND	ND
Benzo(a)Pyrene	1	ND	ND
Benzo(g,h,i)Perylene	2.5	ND	ND
Chrysene	1	ND	ND
Fluoranthene	1	ND	ND
Fluorene	1	ND	ND
Indeno(1,2,3-cd)Pyrene and Dibenz(a,h)Anthracene	3	ND	ND
Naphthalene	1	ND	ND
Phenanthrene	1	ND	ND
Pyrene	1	ND	ND

## ANALYTICAL RESULTS OF GROUNDWATER SAMPLES

<i>Compound</i>	<i>MDL</i>	<i>OW14-90</i>	<i>OW15-90</i>
<i>VOCs (µg/L)</i>			
Benzene	1	ND	ND
Bromodichloromethane	1	ND	ND
Bromoform	2	ND	ND
Bromomethane	10	ND	ND
Carbon Tetrachloride	2	ND	ND
Chlorobenzene	1	ND	ND
Chloroethane	10	ND	ND
2-Chloroethyl Vinyl Ether	10	ND	ND
Chloroform	1	4.3	ND
Chloromethane	10	ND	ND
Dibromochloromethane	1	ND	ND
Dibromoethane	4	ND	ND
1,2-Dichlorobenzene	1	ND	ND
1,3-Dichlorobenzene	1	ND	ND
1,4-Dichlorobenzene	1	ND	ND
1,1-Dichloroethylene	1	ND	ND
1,1-Dichloroethane	1	ND	ND
1,2-Dichloroethane	2	ND	ND
trans-1,2-Dichloroethylene	1	ND	ND
Dichloromethane	5	ND	ND
1,2-Dichloropropane	1	ND	ND
cis-1,3-Dichloropropene	1	ND	ND
trans-1,3-Dichloropropene	1	ND	ND
Ethylbenzene	1	1.1	ND
A-Methylstyrene	1	ND	ND
Methylstyrene Isomers	1	ND	ND
Mesitylene	1	ND	ND
Styrene	2	ND	ND
1,1,2,2-Tetrachloroethane	2	ND	ND
Tetrachloroethylene	1	ND	ND
Toluene	2	ND	ND
1,1,1-Trichloroethane	2	ND	ND
1,1,2-Trichloroethane	1	ND	ND
Trichloroethylene	1	ND	ND
Trichlorofluoromethane	2	ND	ND
m+p Xylene	2	TR	ND
o-Xylene	1	1.5	ND
Vinyl Chloride	5	ND	ND
Other Aromatic Compounds	1	16	ND

## Notes:

1. ND = Not Detected
2. TR = Trace
3. Other aromatic compounds = total concentration of tri- and tetramethylbenzenes using the response factor of mesitylene.



likely have had underground storage tanks which could have leaked into the ground in the past.

The non-aqueous phase liquids which are encountered in the boreholes and at well locations OW8-87 and OW17-90 represent a potential source of groundwater contamination. The ultimate discharge point of groundwater is undefined, however it appears that coal tar material in the saturated soil zone does not readily solubilize into groundwater and migrate, as evidenced by the analytical results of soil and water samples from monitoring wells OW14-90 and OW15-90.

### 5.3 GRAND RIVER WATER AND SEDIMENT

The underwater inspection of the Grand River was carried out over a 50 metre by 50 metre area as shown on Figure 3.1 presented previously. The intensity of the search pattern by the diver was greatest near the shore as discussed in the report by Integrated Explorations (Appendix A). The diver visually observed the bottom sediments and used white plastic probes driven 75 to 150 millimetres into the soil every 0.6 to 1.0 metres to detect any buried coal tar. Coal tar, if any is present, which contacts the probe is made visible on the probe due to the affinity of oils for the plastic and the propensity to spread as a thin film over the plastic surface. In addition, seven holes were cut in the ice and underlying sediments were agitated with a pole to observe a possible oil sheen.

There were no observances of coal tar or oil material in water or sediments through the efforts described above. Therefore, it is considered that coal tar contamination does not exist in the survey area, which is the most probable area in the river for this material to appear in relation to the former coal gasification plant.

As part of the December 1988 river inspection, two surface water and three sediment samples were collected and analyzed for PAHs. In addition, two water samples were collected in May 1990 and analyzed for PAHs. Sample locations are shown on Figure 3.1 presented previously. The water samples were collected from approximately 20 cm above the river bottom.

Analytical results for sediment and water samples are contained in Tables 5.9 and 5.10, respectively. Sediment samples S-1 and S-2 were collected within the river inspection area. These samples contain low concentrations of various PAHs. The total concentrations of PAHs in these samples were 4.42 ppm in S-1, 4.16 ppm in S-1 duplicate and 1.93 ppm in S-2. Sediment sample S-3 was collected upstream of the survey area and just downstream of a storm outfall pipe. The total concentration of PAHs in this sample was 5.66 ppm. The concentrations of PAHs at all three sampling locations are similar.

Sample S-3 is considered to be representative of background conditions in the Grand River near the property. The boreholes drilled during the geotechnical investigation adjacent to the area of sample S-3 (i.e. BH205, 206, 207) did not encounter any coal tar deposits based on

**TABLE 5.9**  
**ANALYTICAL RESULTS OF GRAND RIVER SEDIMENT SAMPLES**

<i>Compound (ppm)</i>	<i>MDL</i>	<i>S-1</i>	<i>S-1 (Dup)</i>	<i>S-2</i>	<i>S-3</i>
Acenaphthene	0.02	ND	ND	0.02	0.02
Acenaphthylene	0.02	ND	ND	ND	ND
Anthracene	0.02	0.03	0.06	0.03	0.1
Benz(a)Anthracene	0.02	0.3	0.3	0.1	0.2
Benzo(b)Fluoranthene and Benzo(k)Fluoranthene	0.02	1.0	0.9	0.4	1.1
Benzo(a)Pyrene	0.02	0.5	0.4	0.1	0.7
Benzo(g,h,i)Perylene	0.04	0.2	0.3	0.1	0.4
Chrysene	0.02	0.6	0.5	0.1	0.5
Dibenz(a,h)Anthracene	0.04	0.09	0.1	TR	0.1
Fluoranthene	0.02	0.6	0.6	0.4	0.9
Fluorene	0.02	ND	ND	ND	0.04
Indeno(1,2,3-cd)Pyrene	0.04	0.2	0.2	0.08	0.3
Naphthalene	0.02	ND	ND	ND	ND
Phenanthrene	0.02	0.3	0.2	0.2	0.5
Pyrene	0.02	0.6	0.6	0.4	0.8

Notes:

ND - Not Detected

TR - Trace

MDL - Method Detection Limit

TABLE 5.10

## ANALYTICAL RESULTS OF GRAND RIVER WATER SAMPLES

<i>Compound (µg/L)</i>	<i>MDL (1)</i>	<i>W-1</i>	<i>W-2</i>	<i>MDL (2)</i>	<i>W-3</i>	<i>W-4</i>
Acenaphthene	0.05	ND	ND	1.2	ND	ND
Acenaphthylene	0.05	ND	ND	1.5	ND	ND
Anthracene	0.05	ND	ND	2	ND	ND
Benz(a)Anthracene	0.05	ND	ND	2	ND	ND
Benzo(b)Fluoranthene and Benzo(k)Fluoranthene	0.05	0.06	ND	4	ND	ND
Benzo(a)Pyrene	0.05	ND	ND	3	ND	ND
Benzo(g,h,i)Perylene	0.1	ND	ND	5	ND	ND
Chrysene	0.05	ND	ND	2	ND	ND
Dibenz(a,h)Anthracene	0.1	ND	ND	NA	NA	NA
Fluoranthene	0.05	0.06	ND	2	ND	ND
Fluorene	0.05	ND	ND	1.5	ND	ND
Indeno(1,2,3-cd)Pyrene	0.1	ND	ND	NA	NA	NA
Naphthalene	0.05	ND	ND	1.2	ND	ND
Phenanthrene	0.05	ND	ND	2	ND	ND
Pyrene	0.05	ND	ND	1.5	ND	ND
Dibenz (a,h) Anthracene and Indeno (1,2,3-cd)Pyrene	NA	NA	NA	8	ND	ND

Notes:

ND - Not Detected

NA - Not Applicable

(1) Method Detection Limit for samples W-1 and W-2

(2) Method Detection Limit for samples W-3 and W-4

visual and olfactory observations. It would be expected that PAHs would be found in the river sediments because of the developed nature of the area and the many potential sources of PAHs in a developed area. A study of typical concentrations of PAHs in the environment by the MOE (5) indicated the presence of benzo (a) pyrene in soils and sediments near a highway at 2 ppm. It would be expected that similar concentrations may be encountered near roadways in the watershed of the Grand River. These sediments would then be expected to migrate to the river. Therefore, the concentration of PAHs found in the Grand River sediment samples could be expected to result from background activities.

The water sample collected in December 1988 adjacent to the former coal gasification plant (just upstream of sediment sample location S-2) showed two detections; benzo(b)fluoranthene/benzo(k)fluoranthene at 0.06 µg/L and fluoranthene at 0.06 µg/L. These values are slightly above the detection limit of 0.05 µg/L. These compounds were also detected in all three sediment samples which were analyzed. It is possible that these compounds were present in the water sample as a result of suspended sediments containing PAHs. The sediments may have become suspended by the movement of the diver.

The water sample collected in May 1990 adjacent to the former coal gasification plant did not contain detectable quantities of PAHs. This sample was collected without any agitation of sediments. These results may be more indicative of the water quality in the Grand River near the former coal gasification plant than the earlier results.

PAHs were not detected in the water samples which were collected in December 1988 and May 1990 upstream of the former coal gasification plant.

## 6.0 CONCLUSIONS AND RECOMMENDATIONS

### 6.1 CONCLUSIONS

Based on the information presented in this report, the following conclusions are made:

- 1) The material underlying the former coal gasification plant includes concrete and soil containing coal tar residues. Gasoline and diesel fuel odours are also noted in this area.
- 2) Coal tar residues are present in soil to the west of the former coal gasification plant. These residues are found sporadically and may have been placed in part during historical filling along the edge of the Grand River.
- 3) Coal tar residues are present in soil beneath the GRCA flood control berm.
- 4) The coal tar residues are generally found in the saturated soils and represent a potential source of groundwater contamination.
- 5) Groundwater flow on the property appears to be approximately parallel to the Grand River and toward the south.
- 6) Groundwater at the southern end of the property does not exhibit contamination by PAHs. One monitoring well exhibits low

concentrations of VOCs. The VOC contamination has various potential sources, including the coal tar residues and former automobile service stations in the area.

- 7) Coal tar residues have not migrated to the southern property boundary as evidenced by the absence of PAHs in soil and groundwater at the two monitoring wells at the boundary.
- 8) Coal tar residues are not visually present in the bed of the Grand River adjacent to the former coal gasification plant.
- 9) Water and sediment in the Grand River does not exhibit a detectable impact by PAHs from the former coal gasification plant.

## 6.2 RECOMMENDATIONS

Based on the above, the following recommendations are made:


- 1) Any proposed disturbance of the area containing coal tar residues should be reported in writing to the MOE, Waste Management Branch prior to commencement and conducted in accordance with applicable regulations and guidelines.




- 2) A monitoring program should be implemented in the short term to assess the potential migration of contaminants in groundwater and surface water. This would include:
- i) measuring water levels in the monitoring wells and the Grand River quarterly for one year;
  - ii) collecting water samples from wells which do not contain coal tar and from two locations in the Grand River on a semi-annual basis for one year (groundwater samples would be analyzed for PAHs and VOCs, surface water samples would be analyzed for PAHs); and
  - iii) reporting all results to the MOE.

The need for monitoring would be re-assessed at the end of the one year period.

All of Which is Respectfully Submitted,  
CONESTOGA-ROVERS & ASSOCIATES

A handwritten signature in cursive script that reads "Don Haycock". The signature is fluid and stylized, with a large loop at the end of the last name.

Donald H. Haycock, P. Eng.

A handwritten signature in cursive script that reads "Julian Hayward". The signature is fluid and stylized, with a large loop at the end of the last name.

Julian Hayward, P. Eng.

## REFERENCES

- 1) Proposal for Additional Investigative Work, Former Galt Gas Co. Site, Conestoga-Rovers & Associates, June 1989.
- 2) Subsurface Investigation, Former Galt Gas Co. Site, Conestoga-Rovers & Associates, September 1987.
- 3) Guidelines for the Decommissioning and Clean-up of Sites in Ontario, Ontario Ministry of the Environment, January 1989.
- 4) Hvorsiev, M. J. 1951. Time lag and soil permeability in groundwater observations. U.S. Army Corps Engrs. Waterways Exp. Sta. Bull. 36, Vicksburg, Miss.
- 5) Polynuclear Aromatic Hydrocarbons, A Background Report Including Available Ontario Data, ARB-TDA-Report No. 58-79, Ministry of the Environment, Air Resources Branch, Technology Development and Appraisal Section, September 1979.



## APPENDIX A


### GRAND RIVER INSPECTION REPORT BY INTEGRATED EXPLORATIONS

DIVING INSPECTION OF COAL TAR SITE IN  
THE GRAND RIVER, CAMBRIDGE (GALT), ONTARIO

Report No. PJ8818-1

December 29, 1988

REPORT PREPARED BY -

  
Al Melkic,

DIVING INSPECTION OF COAL TAR SITE IN  
THE GRAND RIVER, CAMBRIDGE (GALT), ONTARIO

INTRODUCTION *JH*

On December <sup>16</sup>~~18~~, 1988, Integrated Explorations conducted an underwater inspection of the area suspected of harbouring coal tar in the Grand River. The site was adjacent to the area known as the "Mill Race on the Grand", and located on the east bank, south of the Samuelson railway bridge in Cambridge (Galt). The purpose of the dive was to survey an area bounded by a 50 by 50 meter square for signs of coal tar using visual and coal tar probing methods. Some representative samples of water and sediment were also collected from the area.

Those involved in the project included the following: Mr. Julian Hayward who directed the survey, Mr. Al Melkic, who supervised the dive team and acted as stand by diver, Mr. Yves Rollin who worked as our primary diver, and Mr. Christopher Wade who functioned as the dive tender. Also, various OMOE officials dropped in briefly to observe our survey operation.

SITE OBSERVATIONS

1 - AREA SURVEYED is illustrated in the attached survey plan. It was bounded by a 50 by 50 meter square. As illustrated in our drawing, the diver conducted an intensive search near shore and a looser but more extensive search as he proceeded towards the middle of the river. This is a standard procedure as contaminants entering rivers from the land are usually found close to shore.

2 - DIVING CONDITIONS included ice cover of 4 to 6 inches and two feet visibility. Observations made by the diver were relayed to the surface crew. Ice holes were cut in strategic places to allow the diver to verify his position with respect to surface transect lines which were layed out over the surface of the ice.

3 - TAR PROBING TECHNIQUE was used to aid visual inspection as buried coal tar is difficult to distinguish from silt and clay. Technical notes pertaining to the coal tar probing methodology are appended to this report.

4 - PRESENCE OF COAL TAR was not indicated anywhere in our survey. Our experience from other coal tar surveys would lead us to believe that there is no coal tar present in the area. It should be noted that even if coal tar is hidden beneath superficial sediments, the movement of the diver and his umbilical line combined with the continual probing of the sediments would be sufficient to reveal such deposits.

5 - RIVER SUBSTRATE was characterized by cobbles and boulders within 5 to 7 meters from shore. These were covered with a light silt varying between 0 to 15 cm in thickness. Further out from shore where the depth approached 6 ft. the bottom substrate changed to between 2 1/2 and 5 cm of silt cover over gravel with a clay substrata. Some areas were encountered where the tar probe could be pushed 36 cm into the soft sediment.

6 - SEDIMENT AND WATER SAMPLES were collected at points depicted in the survey sketch map attached to this report. The two water samples were collected at a height of 20 cm from the river bottom. The three sediment samples were collected by scraping material directly into the sampling jars.

---



## Technical Notes Regarding Novel Tar Probing Technology


Integrated Explorations has developed a number of techniques for quickly estimating the extent of underwater coal tar deposits without resorting to costly chemical analysis. Some of these techniques were used to develop the first map delineating the coal tar spill site in the Rideau River in 1986. This methodology was later improved upon and used with great success at the Port Stanley site in 1987. Currently the probing technique is being used in the Trent River to explore for creosote contamination in outlying areas for the Kingston Regional MOE. In February of 1989 our firm will be using this probing method to delineate the extent of a coal tar contaminated site in Owen Sound for the London Regional Ministry of the Environment.

With this method, oily and tar-like substances occurring as minute specks are made visible by virtue of their affinity for the plastic probe and their propensity to spread as a thin film over such surfaces. This provides a distinct advantage in detecting tiny specks covered by sediments. It also makes it easier to spatially resolve contaminated areas by providing a large number of visual indications per unit area without having to retrieve actual samples except for verification. With this technique, a diver can also distinguish between tar-like substances and clay which in our experience has always presented difficulties underwater.

---

# DIVER SEARCH PATTERNS USED AT GALT SITE DEC. 16th, 1988

(UNDER ICE DIVE)



GRAND RIVER CURRENT

GRAND RIVER CURRENT

SHORELINE

SHORELINE

S-3

S-2

S-1

Sample point

MAIN ICE HOLE FOR DIVING (7m from Shore)

SAMPLING POINTS → ① - Sediment #1

→ ② - Sediment #2, water #1

→ ③ - Sediment #3, water #2

Sample numbers

## APPENDIX B

### FIELD METHODS FOR PHASE IV INVESTIGATION

## 1.0 FIELD INVESTIGATION

The Phase IV field investigation program was conducted during the period of February 5, 1990 to May 3, 1990. This program consisted of the installation of three groundwater monitoring wells, completion of five soil boreholes, soil sampling of the groundwater monitoring wells and soil boreholes, monitoring of water levels at four groundwater monitoring well locations and two river level stations, groundwater and river water sampling and level surveying of the installed groundwater monitoring wells and soil boreholes. A detailed description of these tasks follows.

### 1.1 GROUNDWATER MONITORING WELL INSTALLATION

The firm of Strata Drilling Incorporated of Cambridge, Ontario, was retained by CRA to install three groundwater monitoring wells; OW14-90, OW15-90 and OW17-90 (Figure 3.1, previous). The boreholes were advanced utilizing a CME-55 truck-mounted drill rig equipped with 4-1/4 inch I.D. hollow stem augers. During the course of the drilling operation split-spoon samples of the soils were collected at 2.5 foot intervals in order to assess the stratigraphic sequences at each of the boreholes. The soil samples were examined and the descriptions logged by a qualified CRA technician. Blow counts for Standard Penetration Tests (SPT) were also recorded during the soil sampling event. The recovered soil samples were labeled as to sample interval and location and retained for future reference.

Once the desired borehole depth had been achieved, groundwater monitoring wells were installed into the borehole. Construction of the groundwater monitoring wells consisted of a 4.0 foot length of #10 slot, 2 inch diameter, stainless steel well screen connected by coupled 2 inch diameter black iron riser pipe. Construction details for the groundwater monitoring wells installed during the Phase IV investigation are provided in Table B-1.

The groundwater monitoring well installations were completed with a native sand pack caved to a minimum height of 2.0 feet above the top of the screen. The remaining annular space was filled with a mixture of cuttings and bentonite grout to within 2.0 feet of the surface which was subsequently filled with concrete. A protective steel casing was placed over the groundwater monitoring well and set into the concrete to complete the installation.

## 1.2 SOIL BOREHOLES

The firm of Strata Drilling Incorporated was also retained by CRA to complete five soil boreholes; BH16-90, BH18-90, BH19-90, BH20-90 and BH21-90 (Figure 3.1, previous). Each of these boreholes was advanced to the desired depth utilizing the equipment and methods employed during the installation of the groundwater monitoring wells. As previously, during the course of the drilling operations, split-spoon samples of the soils were collected at 2.5 foot intervals in order to assess the stratigraphic sequences at each of the boreholes. The retrieved soil samples were examined and the

**TABLE B-1**  
**MONITORING WELL COMPLETION DETAILS**

<i>Well Number</i>	<i>Ground Elevation (m AMSL)</i>	<i>Reference Elevation (m AMSL)</i>	<i>Total Depth (m)</i>	<i>Screened Interval Elevation (m AMSL)</i>	<i>Screened Interval Depth (m)</i>	<i>Screened Material</i>
OW14-90	267.541	268.409	5.79	263.84 - 262.62	4.57 - 5.79	sand
OW15-90	267.639	268.542	5.49	264.27 - 263.05	4.27 - 5.49	sand
OW17-90	268.484	269.560	5.83	264.95 - 263.73	4.61 - 5.83	sand

descriptions logged by a qualified CRA technician. Blow counts for Standard Penetration Tests (SPT) were also recorded during the soil sampling events. The recovered soil samples were labeled as to the sample interval and location and retained by CRA for future reference.

Upon completion of the borehole to the desired depth, the borehole was backfilled using only clean cuttings. The remaining annular space was then grouted using a bentonite grout to within 2.0 feet of the surface, which was subsequently filled with concrete to provide a good surface seal.

In order to prevent any form of cross-contamination from borehole to borehole, the drilling rig and all equipment was washed using a high pressure, hot water (steam) washer. The wash water was collected in a trough and pumped to 45 gallon drums for future disposal.

### 1.3 SOIL SAMPLING

During the course of the drilling operations for the groundwater monitoring wells and the soil boreholes, soil samples were collected at 2.5 foot intervals, using split-spoon sampling techniques. The recovered soil samples were examined and the descriptions logged by a qualified CRA technician. The soil samples were retained in precleaned laboratory glass jars and labeled as to the sample interval and location. Soil samples selected for laboratory analysis were packed on ice in a secure chest

and shipped via courier to the contract laboratory. Chain-of-Custody forms accompanied each shipment.

In order to prevent any cross-contamination between successive soil samples and prior to taking of the first soil sample, the split-spoon sampling device was cleaned using a clean water wash followed by a distilled water rinse, a methanol rinse and a final distilled water rinse.

#### 1.4 GROUNDWATER SAMPLING

Prior to groundwater sampling, each groundwater monitoring well was developed by removing a minimum of five standing well volumes of groundwater from the well using a Wattera pump and polytubing set within the well casing. Stabilization criteria were met when two consistent measurements of pH and conductivity were recorded. Observations of color, turbidity and odor were also noted during the well development and are presented in Table B-2 along with the aforementioned development criteria.

Once the groundwater monitoring wells had been suitably developed, two groundwater samples were collected from each of the wells. The first sample, for Volatile Organic Compounds (VOC), was collected in a 40-ml laboratory glass vial. A second sample, for Polynuclear Aromatic Hydrocarbons (PAH), was collected in a 1-litre amber glass container. All samples were assigned a unique sample number, packed on ice in a secure



TABLE B-2

## WELL DEVELOPMENT AND STABILIZATION PARAMETERS

Well Number	Well Volume (l)	Volume Removed (l)	pH	Conductivity (umhos/cm)	Clarity	Colour	Odour	Comments
OW14-90	4.0	9.0	6.0	1020	very turbid	brown	none	moderate recharge
		4.0	6.3	1020	very turbid	brown	none	moderate recharge
		4.0	6.4	1020	very turbid	brown	none	moderate recharge
		4.0	6.4	1020	very turbid	brown	none	moderate recharge
OW15-90	3.0	4.5	6.67	920	very turbid	dark grey	none	contains silty sands
		2.0	6.67	920	very turbid	dark grey	none	contains silty sands
		3.0	7.07	920	very turbid	dark grey	none	contains silty sands
OW17-90	2.0	3.0	6.7	1020	very turbid	black	moderate coal tar	sheen, moderate recharge
		3.0	6.7	1040	very turbid	black	moderate coal tar	sheen, moderate recharge
		3.0	6.6	1040	very turbid	grey	moderate coal tar	sheen, moderate recharge
		3.0	6.6	1040	very turbid	grey	moderate coal tar	sheen, moderate recharge

chest and shipped via courier to the contract laboratory. A chain-of-custody form accompanied the shipment of samples.

## 1.5 RIVER WATER SAMPLING

Water samples from the Grand River were collected on May 3, 1990, at two locations, approximately 20 cm above the river bed. The method employed in order to retrieve the river water samples consisted of securing a rubber stopper sealed, 1-litre, amber glass bottle to a long pole with tape. The bottle was then placed into the river, approximately 10 feet from shore, such that the bottle was upright and the base of the bottle rested on the river bed. The rubber stopper was then removed allowing the bottle to fill. The retrieved sample was then assigned a unique sample number, packed on ice in a secure chest and shipped via courier to the contract laboratory. A chain-of-custody form accompanied the shipment.

## 1.6 WATER LEVEL MONITORING

During the course of the Phase IV investigation, groundwater elevations were measured in groundwater monitoring wells; OW8-87, OW14-90, OW15-90 and OW17-90 on several occasions (see Table 4.1, previous). The water levels were obtained using a Solinst water level indicator which emits an audible signal when the probe comes in contact with the water surface. The probe is attached to a flat embossed tape, calibrated to 1 cm intervals, which allows for accurate water level readings to

within 2 mm. In order to avoid any cross-contamination between groundwater monitoring wells and prior to the first reading, the stainless steel probe was washed with a methanol and distilled water rinse.

## 1.7 LEVEL SURVEY

In order to establish horizontal and vertical control, CRA conducted a level survey of the groundwater monitoring wells and boreholes in February 1990. The reference and ground elevations are included on the stratigraphic and instrumentation logs in Appendix C.

## 1.8 SINGLE WELL RESPONSE TESTS

Single well response tests were conducted on two groundwater monitoring wells; OW14-90 and OW15-90. The method employed in the tests involved displacing the groundwater within the well casing with a slug of known volume and monitoring the water levels, over time, as they returned to the static level. The recorded data was then analyzed following methods outlined by Hvorslev (1951) to determine the hydraulic conductivity.



## APPENDIX C

### BOREHOLE LOGS

# SOIL CLASSIFICATION SYSTEM (MODIFIED U.S.C.)

MAJOR DIVISION		GROUP SYMBOL	TYPICAL DESCRIPTION
HIGHLY ORGANIC SOILS		PI	PEAT AND OTHER HIGHLY ORGANIC SOILS
COARSE GRAINED SOILS (MORE THAN HALF BY WEIGHT LARGER THAN NO. 200 SIEVE SIZE)	GRAVELS MORE THAN HALF COARSE FRACTION LARGER THAN NO. 4 SIEVE SIZE	CLEAN GRAVELS	GW WELL-GRADED GRAVELS, GRAVEL-SAND MIXTURES, < 5% FINES
			GP POORLY-GRADED GRAVELS, AND GRAVEL-SAND MIXTURES, < 5% FINES
		DIRTY GRAVELS	GM SILTY GRAVELS, GRAVEL-SAND-SILT MIXTURES > 12% FINES
			GC CLAYEY GRAVELS, GRAVEL-SAND-CLAY MIXTURES > 12% FINES
	SANDS MORE THAN HALF COARSE FRACTION SMALLER THAN NO. 4 SIEVE SIZE	CLEAN SANDS	SW WELL-GRADED SANDS, GRAVELLY SANDS, < 5% FINES
			SP POORLY-GRADED SANDS, OR GRAVELLY SANDS, < 5% FINES
		DIRTY SANDS	SM SILTY SANDS, SAND-SILT MIXTURES > 12% FINES
			SC CLAYEY SANDS, SAND-CLAY MIXTURES > 12% FINES
FINE-GRAINED SOILS (MORE THAN HALF BY WEIGHT PASSES NO. 60 SIEVE SIZE)	SILTS BELOW "A" LINE ON PLASTICITY CHART; NEGLECTIBLE ORGANIC CONTENT	ML	INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY SANDS OF SLIGHT PLASTICITY
		MH	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS, FINE SANDY OR SILTY SOILS
	CLAYS ABOVE "A" LINE ON PLASTICITY CHART; NEGLECTIBLE ORGANIC CONTENT	CL	INORGANIC CLAYS OF LOW PLASTICITY, GRAVELLY, SANDY, OR SILTY CLAYS, LEAN CLAYS
		CI	INORGANIC CLAYS OF MEDIUM PLASTICITY SILTY CLAYS
		CH	INORGANIC CLAYS OF HIGH PLASTICITY, FAT CLAYS
	ORGANIC SILTS & ORGANIC CLAYS BELOW "A" LINE ON PLASTICITY CHART	OL	ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY
		OH	ORGANIC CLAYS OF HIGH PLASTICITY

# STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

(L-7)

PROJECT NAME: FORMER GALT GAS CO. SITE

HOLE DESIGNATION: BH-1-87

PROJECT NO.: 2087


DATE COMPLETED: MARCH 16, 1987

CLIENT: MILLRACE ON THE GRAND INC.

DRILLING METHOD: SOLD AUGER

LOCATION: AS PER PLAN

CRA SUPERVISOR: B. FODY

DEPTH m BG	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEVATION m AMSL	MONITOR INSTALLATION	SAMPLE		
				GRAIN SIZE	TEST	ANALYSIS
	GROUND SURFACE	268.43				
	CONCRETE FLOOR SLAB	268.03				
1.0	GW GRAVEL (Fill): some sand, maximum aggregate size: 20 mm dia., compact, brown, moist	267.23				
2.0	SM SAND (Fill): some silt, little gravel, poorly graded, medium grained, dense, brown, moist	266.23				
3.0	SM SAND: some silt, poorly graded, medium grained, dense, brown, moist					
4.0	- becomes water saturated with occasional thin seams of coarse SP.	264.43				
5.0	END OF HOLE @ 4.90 m BGS.	263.53				
6.0						
7.0						
8.0						
9.0						
10.0						
11.0						
12.0						
13.0						

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

GRAIN SIZE ANALYSIS



WATER FOUND



STATIC WATER LEVEL



(16/03/87)

# STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

(L-2)

PROJECT NAME: FORMER GALT GAS CO. SITE

HOLE DESIGNATION: B-2-87

PROJECT NO.: 2087


DATE COMPLETED: MARCH 16, 1987

CLIENT: MILLRACE ON THE GRAND INC.

DRILLING METHOD: 95mm D - SA

LOCATION: AS PER PLAN

CRA SUPERVISOR: B. FEDY

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEVATION m AMSL	MONITOR INSTALLATION	SAMPLE		
				NUMBER	STATUS	ANALYSIS
	GROUND SURFACE	268.44				
	CONCRETE FLOOR SLAB	268.04				
1.0	GW GRAVEL (Fill): same sand, compact, brown, moist	267.44		1SS	X	10
2.0	SM SAND (Fill): some silt, trace clay, fine grained, compact, brown, moist	266.64		2SS	X	14
3.0	SM SAND: some silt, layered, dilatent, low to non-plastic, compact, brown, moist, occasional layer of medium grained SP	265.44		3SS	X	55
4.0	SP SAND: trace silt, trace fine gravel, layered, medium grained, very dense, brown, moist	264.44		4SS	X	28
5.0	SP SAND: uniform, layered, becomes grey, water saturated - strong coal tar odour	263.84		5SS	X	26
5.0	END OF HOLE @ 5.20 m BGS.	263.24		6SS	X	18
6.0						
7.0						
8.0						
9.0						
10.0						
11.0						
12.0						
13.0						

## NOTES:

MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

GRAIN SIZE ANALYSIS



WATER FOUND



STATIC WATER LEVEL



(16/03/87)



# STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

(L-9)

PROJECT NAME: FORMER GALT GAS CO. SITE

HOLE DESIGNATION: B-3-87

PROJECT NO.: 2087

DATE COMPLETED: MARCH 16, 1987

CLIENT: MILLRACE ON THE GRAND INC.

DRILLING METHOD: 95mm ID - SA

LOCATION: AS PER PLAN

CRA SUPERVISOR: B. FEDY

DEPTH m BG	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEVATION m AMSL	MONITOR INSTALLATION	SAMPLE		
				UNIT DEPT	SIZE CLASS	DEPTH m
	GROUND SURFACE	267.06				
	CONCRETE FLOOR SLAB					
1.0	GW GRAVEL (Fill): some sand, compact, brown, moist, becomes black with occasional coal fragments	266.66		1SS	<input checked="" type="checkbox"/>	28
2.0	SP SAND: trace silt, layered, fine grained, dense, brown, moist, becomes siltier, water saturated - thin seam of fine SM, black - grey, strong coal tar odour	265.66		2SS	<input checked="" type="checkbox"/>	25
3.0		264.76		3SS	<input checked="" type="checkbox"/>	29
4.0	- brown/yellow with strong gasoline odour			4SS	<input checked="" type="checkbox"/>	25
4.0	END OF HOLE @ 3.90 m BGS.	263.16				
5.0						
6.0						
7.0						
8.0						
9.0						
10.0						
11.0						
12.0						
13.0						

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

GRAIN SIZE ANALYSIS

WATER FOUND

STATIC WATER LEVEL

(16/03/87)

# STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

(L-2)

PROJECT NAME FORMER GALT GAS CO. SITE  
PROJECT NO. 2057  
CLIENT MILLRACE ON THE GRAND INC  
LOCATION AS PER PLAN

HOLE DESIGNATION B-4-27  
DATE COMPLETED MARCH 6, 1987  
DRILLING METHOD 95mm D HSA  
CRA SUPERVISOR B. FODY

DEPTH m BG	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEVATION m AMSL	MONITOR INSTALLATION	SAMPLE		
				UNIT NO.	TEST NO.	TEST NO.
	GROUND SURFACE	267.04				
	CONCRETE FLOOR SLAB					
1.0	GW GRAVEL (Fill): some sand, occasional coal fragments, bricks and other rubble, loose, brown to black, moist	266.64		1SS	<input checked="" type="checkbox"/>	20
2.0	SW-SM SAND (Fill): some gravel, some silt, some flyash, occasional pebbles, wood fragments, slag, compact, white to brown, moist	265.64		2SS	<input checked="" type="checkbox"/>	37
3.0	SM SAND: some silt, poorly graded, fine to medium grained, compact, brown, water saturated	264.75 264.64		3SS	<input checked="" type="checkbox"/>	14
4.0	SP SAND: some gravel, medium to coarse grained, compact, grey to yellow, water saturated, strong gasoline odour	263.99 263.24		4SS	<input checked="" type="checkbox"/>	16
	END OF HOLE @ 3.80 m BGS.					
5.0						
6.0						
7.0						
8.0						
9.0						
10.0						
11.0						
12.0						
13.0						

NOTES:

MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

GRAIN SIZE ANALYSIS

WATER FOUND

STATIC WATER LEVEL

(16/03/87)

# STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

PROJECT NAME: FORMER GALT GAS CO. SITE  
PROJECT NO.: 2087  
CLIENT: MILLRACE ON THE GRAND INC.  
LOCATION: AS PER PLAN

HOLE DESIGNATION: B-S-87  
DATE COMPLETED: MARCH 17, 1987  
DRILLING METHOD: 95mm ID HSA  
CRA SUPERVISOR: B. FREDY

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEVATION m AMSL	MONITOR INSTALLATION	SAMPLE		
				GRAIN SIZE ANALYSIS	WATER FOUND	STATIC WATER LEVEL
	GROUND SURFACE	266.59				
	CONCRETE FLOOR SLAB	266.19				
	GW GRAVEL (Fill): some sand, compact, brown, moist	265.79				
1.0	SM SAND (Fill): some silt, little gravel, occasional brick fragments and other rubble, loose, brown to red, dry	265.19		1SS	<input checked="" type="checkbox"/>	9
2.0	SM SAND: some silt, fine grained, uniform, dilatent, layered, oxidized seams, compact, light brown, water saturated			2SS	<input checked="" type="checkbox"/>	13
3.0	- thin seam gravel SG	264.19		3SS	<input checked="" type="checkbox"/>	24
4.0	- thin seam gravel SG			4SS	<input checked="" type="checkbox"/>	18
	END OF HOLE @ 4.20 m BGS.	262.39		5SS	<input checked="" type="checkbox"/>	46
5.0						
6.0						
7.0						
8.0						
9.0						
10.0						
11.0						
12.0						
13.0						

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE  
GRAIN SIZE ANALYSIS WATER FOUND STATIC WATER LEVEL (16/03/87)

# STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

(4-12)

PROJECT NAME: FORMER GALT GAS CO. SITE

HOLE DESIGNATION: B-6-87

PROJECT NO.: 2087


DATE COMPLETED: MARCH 17, 1987

CLIENT: MILLRACE ON THE GRAND INC.

DRILLING METHOD: SOLO AUGER

LOCATION: AS PER PLAN

CRA SUPERVISOR: B. FODY

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEVATION m AMSL	MONITOR INSTALLATION	SAMPLE		
				UNDISTURBED	SLIT	CUT
	GROUND SURFACE	267.04				
	CONCRETE FLOOR SLAB					
1.0	GW GRAVEL (Fill): some sand, occasional pebbles, coal fragments, compact, black, moist.	266.64 266.34	 <p>200mm Ø BOREHOLE</p> <p>CUTTINGS CAPPED WITH BENTONITE PELLETS</p>			
	SG SAND: some gravel, some silt, medium grained, compact, light brown, dry.	265.54 265.24				
2.0	CONCRETE SLAB	264.94				
	ML SILT: some sand, fine grained, cohesive, black, water saturated.	264.54				
3.0	SM SAND: some silt, trace clay, trace gravel, medium grained, grey/black, water saturated, strong coal tar odor.					
4.0	END OF HOLE @ 2.50 m BGS.					
5.0						
6.0						
7.0						
8.0						
9.0						
10.0						
11.0						
12.0						
13.0						

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

GRAIN SIZE ANALYSIS



WATER FOUND



STATIC WATER LEVEL



(16/03/87)

# STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

(L-13)

PROJECT NAME: FORMER GALT GAS CO. SITE  
PROJECT NO.: 2087  
CLIENT: MILLRACE ON THE GRAND INC.  
LOCATION: AS PER PLAN

HOLE DESIGNATION: B-7-87  
DATE COMPLETED: MARCH 17, 1987  
DRILLING METHOD: 95mm D HSA  
CRA SUPERVISOR: B. FEDY

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEVATION m AMSL	MONITOR INSTALLATION	SAMPLE		
				GRAIN SIZE ANALYSIS	STATIC WATER LEVEL	WATER FOUND
	GROUND SURFACE	268.05				
	SM TOPSOIL: organic, black, moist					
1.0	SM SAND (Fill): sand, some silt, occasional coal fragments and rubble, trace flyash and slag, fine grained, loose, brown to yellow, dry, coal smell - moist, dilatent, compact, coal tar odour	267.65		1SS		14
2.0				2SS		15
3.0	SM SAND: some silt, uniform, fine grained, dilatent, layered, oxidized seams, compact to dense, light brown, very moist	265.45		3SS		17
4.0	- water saturated - thin seam of CL, some silt, firm	265.05		4SS		16
				5SS		12
	END OF HOLE @ 4.40 m BGS.	263.65				
5.0						
6.0						
7.0						
8.0						
9.0						
10.0						
11.0						
12.0						
13.0						

**NOTES:**

MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

GRAIN SIZE ANALYSIS



WATER FOUND



STATIC WATER LEVEL



(17/03/87)

# STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

(L-01)

PROJECT NAME: FORMER GALT GAS CO. SITE

HOLE DESIGNATION: QWB-87

PROJECT NO.: 2087


DATE COMPLETED: April 20, 1987

CLIENT: MILL RACE ON THE GRAND INC.

DRILLING METHOD: 108mm I.D. H.S.A.

LOCATION: AS PER PLAN

CRA SUPERVISOR: P. HAYES

DEPTH m BG	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEVATION m AMSL	MONITOR INSTALLATION	SAMPLE		
				DEPTH m	DATE	ANALYSIS
	REFERENCE ELEVATION (Top of riser) GROUND ELEVATION	269.178 268.16		1SS	X	8
1.0	SM - SAND AND SILT (FILL), some gravel, poorly sorted, loose, brown, moist.			2SS	X	7
2.0	- void 2.27m to 2.59m			3SS	X	12
3.0	SP - SAND, some gravel, loose, poorly graded, medium grained, brown, water saturated, weak coal tar odour.	265.26 264.81		4SS	X	4
4.0	- very loose, black, sample is coal tar saturated, strong coal tar odour, split spoon coated in a coal tar water mix, HNU reading downhole 6.8ppm.			5SS	X	14
5.0	- fine grained, poorly graded, loose, sand grains black, sample saturated with coal tar			6SS	X	4
6.0	CL - CLAY, some silt, soft, massive, low plastic, brown, moist, coal tar found as streaks and blebs throughout sample	262.52 262.06		7SS	X	2
7.0	END OF HOLE AT 6.1 m B.G.S.			8SS	X	8
8.0						
9.0						
10.0						
11.0						
12.0						
13.0						

## SCREEN DETAILS

Screened Interval:  
5.18 m to 6.1 m AMSL  
Length - .91 m  
Diameter - 50 mm  
Slot # 10  
Material- Stainless Steel

## NOTES:

MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

GRAIN SIZE ANALYSIS



WATER FOUND



STATIC WATER LEVEL




# STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

L-02

PROJECT NAME: FORMER GALT GAS CO. SITE  
PROJECT NO.: 2057  
CLIENT: MILLRAGE ON THE GRAND INC.  
LOCATION: AS PER PLAN

HOLE DESIGNATION: B-9-87  
DATE COMPLETED: Apr. 20, 1987  
DRILLING METHOD: 108mm I.D. - S.A.  
CRA SUPERVISOR: P. HAYES

DEPTH m BG	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEVATION m AMSL	MONITOR INSTALLATION	SAMPLE		
				SOIL TEMPERATURE	GRAIN ANALYSIS	WATER LEVEL
	GROUND SURFACE	267.04				
	Concrete Floor Slab	266.94	 <p>← 200mm Ø BORE-HOLE</p> <p>← AUGER CUTTINGS</p>	10 SS	4	
1.0	GW - SAND AND GRAVEL (FILL), some red brick fragments, poorly sorted, cohesionless, very dense, brown, moist - slight cool for odor	266.08		25 SS	35	
2.0	- very dense zone, probable concrete side wall of buried tank?	265.24				
3.0	Refused - END OF HOLE AT 1.8m B.G.S. - hole backfilled to surface with auger cuttings					
4.0						
5.0						
6.0						
7.0						
8.0						
9.0						
10.0						
11.0						
12.0						
13.0						

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

GRAIN SIZE ANALYSIS



WATER FOUND



STATIC WATER LEVEL



# STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

L-03;

PROJECT NAME: FORMER SALT GAS CO. SITE

HOLE DESIGNATION: B-HO-87

PROJECT NO.: 2057


DATE COMPLETED: Apr. 21, 1987

CLIENT: WILL RACE ON THE GRAND NC

DRILLING METHOD: 108mm I.D. - S.A.

LOCATION: AS PER PLAN

CRA SUPERVISOR: P. HAYES

DEPTH m BG	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEVATION m AMSL	MONITOR INSTALLATION	SAMPLE		
				NUMBER	STATUS	ANALYSIS
	GROUND SURFACE	267.04				
	Concrete Floor Slab	266.94				
1.0	SM - SAND AND SILT (FILL), some gravel, loose, massive, dark brown, moist.	266.24	 <p>200mm Ø BOREHOLE</p> <p>CEMENT GROUT</p>	1SS	×	6
				2SS	×	3'
2.0	SP - SAND, little gravel, poorly graded, compact, medium grained, brown, moist.			3SS	×	19
	-water saturated	264.76		4SS	×	17
3.0	-black, firm and fluid on sand grains, iridescent green, strong diesel odour.			5SS	×	13
	-slight diesel odour, greyish white sands			6SS	×	3'
4.0	-black, coal tar saturated, strong coal tar odour, MnO reading downhole 2 ppm			7SS	×	13
5.0	SM - SAND, some silt, little clay, compact, fine grained, massive, brown, water saturated	262.32		8SS	×	3'
6.0	GM - GRAVEL, some silt, some sand, some shale limestone fragments, well graded, dense, light brown, water saturated	261.25		9SS	×	48
7.0	Auger Refusal, END OF HOLE AT 7.16 m B.G.S. on probable bedrock	259.88		10SS	×	63
8.0	BOREHOLE GROUTED TO SURFACE UPON COMPLETION					
9.0						
10.0						
11.0						
12.0						
13.0						

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

GRAIN SIZE ANALYSIS ○

WATER FOUND ∑

STATIC WATER LEVEL ▼



# STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

L-04

PROJECT NAME: FORMER GALT GAS CO. SITE

HOLE DESIGNATION: B-H-1-87

PROJECT NO.: 2087

DATE COMPLETED: Apr. 21, 1987

CLIENT: MILL RACE ON THE GRAND INC.

DRILLING METHOD: 108mm ID - HSA

LOCATION: AS PER PLAN

CRA SUPERVISOR: P. HAYES

DEPTH m BG	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEVATION m AMSL	MONITOR INSTALLATION	SAMPLE		
				NUMBER	STATUS	ANALYSIS
	GROUND SURFACE	267.04				
1.0	Concrete Floor Slab GW - SAND AND GRAVEL (FILL), compact, well graded, whitish brown, slightly moist.	266.94	<p>200mm Ø BORE-HOLE</p> <p>CEMENT GROUT</p>	1SS	X	-
		265.52		2SS	X	25
2.0	Concrete Slab	264.91		NO SAMPLE		
	SP - SAND, trace silt, loose to compact, poorly graded, medium grained, mottled brown black, water and diesel saturated, strong diesel odour - trace gravel	264.75		3SS	X	17
3.0				4SS	X	11
4.0	- iridescent sheen to samples, strong diesel odour, downhole HNU 10ppm			5SS	X	23
5.0		262.02		6SS	X	5
	ML - SILT, some sand, little clay, very fine grained, compact, massive, brown, water saturated	261.89		7SS	X	28
6.0				8SS	X	60
7.0	GM - GRAVEL, some silt, some sand, some shaley, limestone fragments, well graded, dense, light brown, water saturated	260.03		9SS	X	100
	Auger Refusal, END OF HOLE AT 7.01m B.G.S. on probable bedrock					
8.0	BOREHOLE GROUTED TO SURFACE UPON COMPLETION					
9.0						
10.0						
11.0						
12.0						
13.0						

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

GRAIN SIZE ANALYSIS



WATER FOUND



STATIC WATER LEVEL



# STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

(1-05)

PROJECT NAME: FORMER GALT GAS CO. SITE

HOLE DESIGNATION: B-12-87

PROJECT NO.: 2087

DATE COMPLETED: Apr. 22, 1987

CLIENT: MILL RACE ON THE GRAND NO.

DRILLING METHOD: 108mm I.D. - S.A.

LOCATION: AS PER PLAN

CRA SUPERVISOR: P. HAYES

DEPTH m BG	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEVATION m AMSL	MONITOR INSTALLATION	SAMPLE		
				DEPTH m BG	TEST TYPE	RESULTS
	GROUND SURFACE	267.05				
	Concrete Floor Slab	266.95		1SS	X	9
1.0	SW - SAND (FILL), some gravel, some red brick fragments, well graded, loose, brown, moist, no chemical odour			2SS	X	5
		265.53				
2.0	SP - SAND, little gravel, medium grained, loose, massive, poorly graded, brown, moist, slight diesel odour, water saturated at 2.13m - black film coating sand grains, strong diesel odour	254.95	Σ	3SS	X	8
3.0				4SS	X	26
	- slight diesel odour			5SS	X	13
4.0	ML - SILT AND SAND, some clay, very fine grained, poorly graded, massive, firm, light brown	262.84		6SS	X	16
5.0	GM - GRAVEL, some silt, some sand, dense, well graded, brown, water saturated	262.02		7SS	X	28
6.0	Auger Refusal, END OF HOLE AT 5.63m B.G.S. on possible bedrock	261.42				
7.0	BORE-HOLE GROUTED TO SURFACE UPON COMPLETION					
8.0						
9.0						
10.0						
11.0						
12.0						
13.0						

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

GRAIN SIZE ANALYSIS



WATER FOUND



STATIC WATER LEVEL



# STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

(L-06)

PROJECT NAME: FORMER GALT GAS CO. SITE

HOLE DESIGNATION: B-13-87

PROJECT NO.: 2087

DATE COMPLETED: April 23, 1987

CLIENT: MILL RACE ON THE GRAND INC.

DRILLING METHOD: 108mm I.D. - S.A.

LOCATION: AS PER PLAN

CRA SUPERVISOR: P. HAYES

DEPTH m BG	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEVATION m AMSL	MONITOR INSTALLATION	SAMPLE		
				GRAIN SIZE	WATER	AVAIL
	GROUND SURFACE	268.34				
	Asphalt	268.28				
1.0	SW - SAND (FILL), little gravel, well graded, loose, massive, brown, moist.					
2.0				1SS	X	9
3.0				2SS	X	5
4.0	SP - SAND, loose, massive, medium grained brown, water saturated -greyish black sands, faint coal tar odour	264.67 264.52		3SS	X	8
5.0	-black, coal tar staining on sand grains, moderate coal tar odour			4SS	X	26
6.0	-sample saturated with coal tar, sample HNU 100ppm			5SS	X	13
	ML-SILT and SAND, some clay, massive, firm, light brown, saturated, coal tar found as stringers between clean silt and sand	262.23		6SS	X	16
7.0	GM-GRAVEL, some silt, some sand, dense, well graded brown, water saturated	261.62		7SS	X	28
	Auger Refusal, END OF HOLE AT 7.32m B.G.S. on possible bedrock	261.01				
8.0						
9.0	BOREHOLE GROUTED TO SURFACE UPON COMPLETION					
10.0						
11.0						
12.0						
13.0						

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

GRAIN SIZE ANALYSIS



WATER FOUND



STATIC WATER LEVEL



# STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

PROJECT NAME: FORMER GALT GAS CO. SITE  
 PROJECT NO.: 2087  
 CLIENT: MILLFACE ON THE GRAND INC.  
 LOCATION: AS PER PLAN

HOLE DESIGNATION: OW-4-90  
 DATE COMPLETED: FEBRUARY 7, 1990  
 DRILLING METHOD: 108mm D - HSA  
 CRA SUPERVISOR: K. VANDERMEULEN

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEVATION m AMSL	MONITOR INSTALLATION	SAMPLE		
				NUM	S	VAL
	REFERENCE ELEVATION (Top of Riser) GROUND ELEVATION	268.409 267.54				
1.0	OL(TOPSOL) SW(SAND)FILL, some sand, little gravel, fine to medium grained, well graded, very dense, brown, moist	267.39	<p>CONCRETE BENTONITE GROUT 203mm BOREHOLE BENTONITE PELLET SEAL SAND PACK 50.8mm BLACK IRON PIPE WELL SCREEN CAVE</p>			
2.0						
3.0						
4.0	SW(SAND), some sand, little gravel, trace to little silt, fine to coarse grained, well graded, very dense, brown	264.46 263.73		1SS	⊗	48
5.0						
6.0				2SS	⊗	>50
7.0						
8.0				3SS	⊗	41
9.0						
10.0	ML(SILT), trace to little sand, fine grained, dilatent, dense, brown, wet, no odour	258.4		4SS	⊗	37
11.0				5SS	⊗	44
12.0	Auger refusal					
13.0	END OF HOLE @ 12.34 m BGS	255.2				
			<p><b>SCREEN DETAILS</b>                      Screened Interval: 4.57m to 5.79m BGS                      Length - 1.22m                      Diameter - 50.8mm                      Slot # 10                      Material - Stainless Steel                      Sand pack interval: 3.72m to 5.79m BGS                      Material - Natural Sand</p>			

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

GRAIN SIZE ANALYSIS ○

WATER FOUND ▽

STATIC WATER LEVEL ▽ (14/03/90)

# STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

(1-5)

PROJECT NAME: FORMER GALT GAS CO. SITE  
PROJECT NO.: 2057  
CLIENT: MILLRACE ON THE GRAND INC.  
LOCATION: AS PER PLAN

HOLE DESIGNATION: OW'S-90  
DATE COMPLETED: FEBRUARY 6, 1990  
DRILLING METHOD: 108mm D HSA  
CRA SUPERVISOR: K. VANDERMEULEN

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEVATION m AMSL	MONITOR INSTALLATION	SAMPLE		
				SYMBOL	SIZE	ANALYSIS
	REFERENCE ELEVATION (Top of Riser) GROUND ELEVATION	268.54 267.64				
1.0	Aspcilt SP(SAND)FILL, some sand, little gravel, trace silt, fine grained, poorly graded, cobbles, dense, brown/black, moist	267.49		1SS	×	25
2.0	Little to trace gravel, little silt, loose, brown			2SS	×	8
3.0	Some sand, little silt, fine grained, loose, brown, moist			3SS	×	7
4.0	Some sand, little gravel, trace silt, fine grained, poorly graded, very dense, metal, brown, moist			4SS	×	50
5.0	SW(SAND), some sands, little to trace gravel, fine to coarse grained, well graded, dense, brown, wet, no odor Little gravel, very dense	264.50 263.83		5SS	×	42
6.0	SW-GW(SAND/GRAVEL), some sand, some gravel, fine to coarse grained, well graded, very dense, brown, wet	262.46		6SS	×	57
7.0				7SS	×	58
8.0	Cabbles			8SS	×	60
9.0	Auger refusal END OF HOLE @ 8.69 m BGS.	258.95		9SS	×	>50
10.0			<b>SCREEN DETAILS:</b> Screened Interval: 4.27m to 5.49m BGS Length - 1.22m Diameter - 50.8mm Slot # 10 Material - Stainless Steel Sand pack interval: 3.51m to 5.49m BGS Material - Natural Sand			
11.0						
12.0						
13.0						

## NOTES:

MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

GRAIN SIZE ANALYSIS



WATER FOUND



STATIC WATER LEVEL




(14/03/90)

# STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

( - 7 )

PROJECT NAME: FORMER GALT GAS CO. SITE  
PROJECT NO.: 2087  
CLIENT: MILLERAGE ON THE GRAND INC.  
LOCATION: AS PER PLAN

HOLE DESIGNATION: B-16-90  
DATE COMPLETED: FEBRUARY 8, 1990  
DRILLING METHOD: 108mm D - HSA  
CRA SUPERVISOR: K. VANDERMEULEN

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEVATION m AMSL	MONITOR INSTALLATION	SAMPLE		
				UNDERTY	SAT	VAL
	GROUND ELEVATION	268.20				
0.0	OL(TOPSOIL) SW(SAND)FILL, some sand, little gravel, fine to medium grained, well graded, dense, cobbles, moist	268.05	 <p>CONCRETE</p> <p>203mm BOREHOLE</p> <p>BENTONITE GROUT</p>			
2.0						
3.0	Little silt, construction material, bricks, rocks, medium dense, brown, wet, no odour or product			1SS	×	20
4.0	Rocks	264.54		2SS	×	23
5.0	Flyash, black, wood, wet, very slight coal tar odour, no product or sheen present			3SS	×	27
6.0	ML(SILT), little to trace sand, trace clay, fine to medium grained, brown/black, wet, slight coal tar odour, water discoloured	262.41 262.10		4SS	×	62
7.0	SW-GW(SAND/GRAVEL), some sand, some gravel, medium coarse grained, well graded, brown, very dense, wet, moderate coal tar odour			5SS	×	57
	Dense, moderate coal tar odour, no product	260.73		6SS	×	39
8.0	END OF HOLE @ 7.47 m BGS.					
9.0						
10.0						
11.0						
12.0						
13.0						

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE: REFER TO CURRENT ELEVATION TABLE

GRAIN SIZE ANALYSIS 

WATER FOUND 

STATIC WATER LEVEL 

# STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

- 6

PROJECT NAME: FORMER GALT GAS CO. SITE

HOLE DESIGNATION: OW17-90

PROJECT NO.: 2087

DATE COMPLETED: FEBRUARY 9, 1990

CLIENT: MILLRACE ON THE GRAND INC.

DRILLING METHOD: 108mm D HSA

LOCATION: AS PER PLAN

GRA SUPERVISOR: K. VANDERVELLEN

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEVATION m AMSL	MONITOR INSTALLATION	SAMPLE		
				INDEX	TYPE	DEPTH
	REFERENCE ELEVATION (Top of Riser) GROUND ELEVATION	269.560 268.484	<p>CONCRETE</p> <p>BENTONITE GROUT</p> <p>203mm BOREHOLE</p> <p>BENTONITE BELL SEAL</p> <p>SAND PACK</p> <p>50.8mm BLACK IRON PIPE</p> <p>WELL SCREEN</p>			
	OL(TOPSOIL)	268.33				
1.0	SW(SAND) FILL, some sand, little gravel, fine to medium grained, dense, cobbles, brown, moist			1SS	×	4'
2.0						
3.0				2SS	×	
4.0		264.54 264.32		3SS	×	20
5.0	OL(SILT), trace fine sand, loose, black, wood chips, decayed vegetation, wet, slight coal tar odour	264.06		4SS	×	5
6.0	SW(SAND), some sand, little gravel, fine to coarse grained, well graded, medium dense, brown, slight coal tar odour, wet	263.3		5SS	×	>30
7.0	ML(SILT), trace fine sand, medium dense, brown, wet	262.08 261.93		6SS	×	>30
8.0	SW(SAND), some sand, little gravel, medium to coarse grained, well graded, medium dense, brown, wet, very slight coal tar odour	261.77				
9.0	END OF HOLE @ 6.71 m BGS					
10.0						
11.0						
12.0						
13.0						

## SCREEN DETAILS

Screened Interval:

4.61m to 5.83m BGS

Length - 1.22m

Diameter - 50.8mm

Slot # 10

Material - Stainless Steel

Sand pack interval:

2.44m to 6.71m BGS

Material - Natural Sand

## NOTES:

MEASURING POINT ELEVATIONS MAY CHANGE: REFER TO CURRENT ELEVATION TABLE

GRAIN SIZE ANALYSIS



WATER FOUND



STATIC WATER LEVEL



(14/03/90)

# STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

(L-01)

PROJECT NAME: FORMER GALT GAS CO. SITE

HOLE DESIGNATION: BH18-90

PROJECT NO.: 3318


DATE COMPLETED: FEBRUARY 9, 1990

CLIENT: MILLRACE ON THE GRAND INC.

DRILLING METHOD: 108mm ID HSA

LOCATION: AS PER PLAN

CRA SUPERVISOR: K. VANDERMEULEN

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEVATION m AMSL	MONITOR INSTALLATION	SAMPLE		
				NUMBER	STATE	ANALYSIS
	GROUND ELEVATION	268.16				
2.5	SW(SAND)FILL, little gravel, trace silt, medium coarse grained, well graded, loose, brown, moist, no odour		 <p>CONCRETE SURFACE SEAL</p> <p>203mm BOREHOLE</p> <p>BENTONITE GROUT</p>	1SS		9
	Little silt, loose, dark brown, wet, no odour	265.27		2SS		2
	Little to some silt, dark brown to black, wet, no odour			3SS		8
5.0	Trace product, strong coal tar odour, sheen, black	262.98		4SS		9
	SP(SAND), trace gravel, fine grained, poorly graded, very loose, black, wet, strong coal tar odour product	261.45		5SS		2
7.5	Trace to little gravel, shell fragments, brown to black, medium dense, wet, coal tar odour	260.08		6SS		18
				7SS		35
				8SS		>50
10.0	SW-CW(SAND/GRAVEL), some sand, some gravel medium to coarse grained, well graded, dense brown, wet, no odour					
12.5	Very dense Auger refusal					
	END OF HOLE @ 8.08 m BGS.					
15.0	NOTES: 1. Contamination approximately 4.57 to 6.4m BGS.					
17.5						
20.0						
22.5						
25.0						
27.5						
30.0						
32.5						

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

GRAIN SIZE ANALYSIS



WATER FOUND



STATIC WATER LEVEL





# STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

(L-02)

PROJECT NAME: FORMER GALT GAS CO. SITE

HOLE DESIGNATION: BH19-90

PROJECT NO.: 3318


DATE COMPLETED: FEBRUARY 7, 1990

CLIENT: MILLRACE ON THE GRAND INC

DRILLING METHOD: 108mm ID -SA

LOCATION: AS PER PLAN

CRA SUPERVISOR: K. VANDERMEULEN

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEVATION m AMSL	MONITOR INSTALLATION	SAMPLE		
				NUMBER	STATE	VALUE
	GROUND ELEVATION	268.17				
2.5	SM(SAND)FILL, some sand, some silt, little gravel, trace clay, fine grained, poorly graded, loose, brown, very moist	265.28	 <p>CONCRETE SURFACE SEAL</p> <p>203mm BOREHOLE</p> <p>BENTONITE GROUT</p>	1SS	⊗	6
5.0	SP(SAND), little silt, trace clay, fine grained, medium dense, brown, wet, no odour or product Dense Medium grained	265.27		2SS	⊗	15
7.5	SM(SAND), little silt, fine grained, poorly graded, medium dense, brown, wet, no odour Thin clay seam at 6.55m BGS, no odour	262.53		3SS	⊗	38
		261.31		4SS	⊗	28
		260.55		5SS	⊗	53
				6SS	⊗	21
				7SS	⊗	>50
10.0	SW-GW(SAND/GRAVEL), some sand, some gravel, medium coarse grained, well graded, medium dense, brown, wet, no odour Very dense					
	END OF HOLE @ 7.62 m BGS. NOTES: 1. Auger refusal at 7.62m BGS.					
12.5						
15.0						
17.5						
20.0						
22.5						
25.0						
27.5						
30.0						
32.5						

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

GRAIN SIZE ANALYSIS



WATER FOUND



STATIC WATER LEVEL



# STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

(L-03)

PROJECT NAME: FORMER GALT GAS CO. SITE

HOLE DESIGNATION: B-20-90

PROJECT NO.: 3318


DATE COMPLETED: FEBRUARY 8, 1990

CLIENT: MILLRACE ON THE GRAND INC.

DRILLING METHOD: 108mm D - SA

LOCATION: AS PER PLAN

CRA SUPERVISOR: K. VANDERMEULEN

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEVATION m AMSL	MONITOR INSTALLATION	SAMPLE		
				SPINDLE LOG	TEST DATA	VELOCITY METER
	GROUND ELEVATION	268.28				
2.5	Asphalt SW(SAND)FILL, some sand, little gravel, fine to medium grained, well graded, cobbles, medium dense, brown, moist, no odour	268.13	 <p>CONCRETE SURFACE SEAL</p> <p>203mm BOREHOLE</p> <p>BENTONITE GROUT</p>	1SS	X	14
		265.23		2SS	X	21
				3SS	X	9
				4SS	X	20
5.0	SP(SAND), some sand, trace silt, fine grained, poorly graded, loose, brown, moist, no odour Product (2.54cm) at 5.79m BGS., sheen, strong coal tar odour	261.88		5SS	X	>30
		261.42		6SS	X	>50
		260.66		7SS	X	>50
7.5	SM(SAND), some sand, some silt, fine grained, poorly graded, brown, dense, wet, slight coal tar odour			8SS	X	17
10.0	SW-GW(SAND/GRAVEL), some sand, some gravel, medium to coarse grained, well graded, medium dense, brown, wet, no odour					
12.5	END OF HOLE @ 7.62 m BGS NOTES: 1. Auger refusal at 7.62m BGS.					
15.0						
17.5						
20.0						
22.5						
25.0						
27.5						
30.0						
32.5						

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

GRAIN SIZE ANALYSIS



WATER FOUND



STATIC WATER LEVEL



# STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

(L-04)

PROJECT NAME: FORMER GALT GAS CO. SITE

HOLE DESIGNATION: BH21-90

PROJECT NO.: 3318


DATE COMPLETED: FEBRUARY 7, 1990

CLIENT: MILLRACE ON THE GRAND INC.

DRILLING METHOD: 108mm ID HSA

LOCATION: AS PER PLAN

CRA SUPERVISOR: K. VANDERMEULEN

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEVATION m AMSL	MONITOR INSTALLATION	SAMPLE		
				DIAPHRAGM	SAT	WATER
	GROUND ELEVATION	268.16				
	Asphalt	268.07				
2.5	SW(SAND)FILL, some sand, little gravel, trace to little silt, fine to medium grained, cobbles, construction material, well graded, very dense, brown, moist, no odour	264.50	 <p>CONCRETE SURFACE SEAL</p> <p>203mm BOREHOLE</p> <p>BENTONITE GROUT</p>	1SS	×	1'
5.0	SW(SAND), some sand, little gravel, fine to coarse grained, well graded, medium dense, brown, wet	264.35		2SS	×	28
7.5	ML(SILT), trace sand, trace clay, fine grained, dilatent, very dense, brown, wet	261.76		3SS	×	>50
	SW-GW(SAND/GRAVEL), some sand, some gravel, fine coarse grained, well graded, rack, brown, wet, no odour or product	260.84		4SS	×	69
10.0	No odour or product Auger refusal	259.17		5SS	×	>50
	END OF HOLE @ 8.99 m BGS.					
12.5						
15.0						
17.5						
20.0						
22.5						
25.0						
27.5						
30.0						
32.5						

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

GRAIN SIZE ANALYSIS



WATER FOUND



STATIC WATER LEVEL



## LOG OF BOREHOLE No. 1

JOB NAME NEWLANDS TEXTILES INC. PROPERTY

JOB NO. 84 F 323


LOCATION 160 WATER STREET NORTH, CAMBRIDGE, ONTARIO

BORING DATE 1984.10.04

ENGINEER D. V. B.

BORING METHOD CONTINUOUS FLIGHT HOLLOW STEM AUGERS


TECHNICIAN P. V. B.



NOTES

CHECKED BY A. A. B.

## LOG OF BOREHOLE No. 2

JOB NAME NEWLANDS TEXTILES INC. PROPERTYJOB NO. 25-5-000LOCATION 160 WATER STREET NORTH, CAMBRIDGE, ONTARIOBORING DATE 1984-10-05ENGINEER E. K. S.BORING METHOD CONTINUOUS FLIGHT HOLLOW STEM AUGERSTECHNICIAN E. K. S.

NOTES Power augered to 42.5 ft., no samples taken below 30.2 ft., soil description based on auger cuttings and observations during drilling.

CHECKED BY ECR

## LOG OF BOREHOLE No. 3

JOB NAME NEWLANDS TEXTILES INC. PROPERTY

LOCATION 160 WATER STREET NORTH, CAMBRIDGE, ONTARIO

BORING DATE 1984.10.05

JOR 84 - 223

ENGINEER D. V. E.

BORING METHOD CONTINUOUS FLIGHT HOLLOW STEM AUGERS

TERRILLIAN, P. V. C.

BORING METHOD		SOIL PROFILE		SAMPLES				SHFAR CTS IN CTM C <sub>0</sub>		LIQUID LIMIT — W <sub>L</sub> PLASTIC LIMIT — P <sub>L</sub> WATER CONTENT — W <sub>P</sub> — L		GROUNDWATER OBSERVATIONS AND REMARKS	
DEPTH ft.	DESCRIPTION	FIELD ELEVATION	ELEVATION	NUMBER	TYPE	BLOWS/FOOT VALUES	DYNAMIC CONE PENETRATION = STANDARD PENETRATION TEST =	BLOWS/FOOT 20 40 60 80	WATER CONTENT — 10 20 30				
	GROUND ELEVATION 876.5												
2.6	FILL: Brown silty sand and gravel fill encountering black cinder fill		875	1	SS			3					
			870	2	SS			3					
				3	SS			6					
12.0	encountering black cinder fill and black coarse sand and gravel to 1 in. diameter some brick rubble, wet		865	4	SS			24					
14.0	ORGANIC SILT: Loose black organic silt, wet			5	SS			7					
15.0	SAND: Loose grey medium-fine sand some organic shells		860	6	SS			9					
17.5	GRAVEL: Very dense grey gravel and coarse sand, wet			7	SS			75/1 in.					
			855	8	SS			80					
			850	9	SS			43					
28.2	borehole terminated at 28.2 ft. Auger refusal on possible boulder or bedrock												

After sample 6  
free water at 11  
ft. inside auger


After sample 8  
free water at 12  
ft. inside auger

Upon completion  
of drilling, no  
free water, cave  
at 6.5 ft.

## VOTES


checked in 5/5/2

## LOG OF BOREHOLE No. 1

JOB NAME NEULANDS TEXTILES INC. PROPERTYLOCATION 160 WATER STREET NORTH, CAMBRIDGE, ONTARIOBORING DATE 1984-10-25BORING METHOD CONTINUOUS FLIGHT HOLLOW STEM AUGERS

NOTES: Power augered to 60.0 ft., no samples taken below 21.5 ft., soil description based on auger cuttings and observations during drilling.

CHECKED BY EA

JOB NAME NEWLANDS TEXTILES INC. PROPERTYJOB No. 14.2LOCATION 160 WATER STREET NORTH, CAMBRIDGE, ONTARIOBORING DATE 1984-10-25ENGINEER B. W. B.BORING METHOD CONTINUOUS FLIGHT MULLER STEIN AUGERTECHNICIAN B. W. B.

## NOTES

- \* Suspect low "N" values caused by excessive differential hydraulic gradient.
- Power augered to 42.5 ft., no samples taken after 27.3 ft., soil description based on auger cuttings and observations during drilling.

CHECKED BY B. W. B.



## LOG OF BOREHOLE No. 6

JOB NAME NEWLANDS TEXTILES INC. PROPERTY

JOB No. 84 F 123


LOCATION 160 WATER STREET NORTH, CAMBRIDGE, ONTARIO

BORING DATE 1984 10 29

ENGINEER P. A. B.

BORING METHOD CONTINUOUS FLIGHT WORMHOLE STEEL AUGERS

TECHNICIAN P. K. B.



NOTES Power augered to 42.5 ft., no samples taken below 25.5 ft., soil description based on auger cuttings and observations during drilling.

CHECKED BY KCB

JOB NAME NEWLANDS TEXTILES INC. PROPERTY

JOB NO. 74 P. 323


LOCATION 160 WATER STREET NORTH, CAMBRIDGE, ONTARIO

BORING DATE 1984.10.09

ENGINEER R. E.

BORING METHOD CONTINUOUS FLIGHT HOLLOW STEM AUGERS

TECHNICAL SKETCH




NOTES

Power augered to 31.0 ft., no samples taken below 21.5 ft., soil description based on auger cuttings and observations during drilling.


CHECKED BY

R. E.

## LOG OF BOREHOLE No 101

JOB NAME PROPOSED MILL RACE CONDOMINIUMSJOB No. 20 F 200LOCATION Water Street North, Cambridge, OntarioBORING DATE 1986.04.28ENGINEER G. M. M. M. M.BORING METHOD Continuous Flight Hollow Stem AugersTECHNICAL C. K. M. M.

NOTES

JOB NAME PROPOSED MILL RACE CONDOMINIUMSJOB N. 86 F 132LOCATION Water Street North, Cambridge, OntarioBORING DATE 1986.04.18ENGINEER G. MitchellBORING METHOD Continuous Flight Hollow Stem AugersTECHNICIAN A. G. G.

NOTES

JOB NAME PROPOSED MILL RACE CONDOMINIUMS \_\_\_\_\_ DATE 25 FEB 1986  
LOCATION Water Street North, Cambridge, Ontario \_\_\_\_\_ BORING DATE 1986.04.22 \_\_\_\_\_ ENGINEER M. J. O'Reilly  
BORING METHOD Continuous Flight Hollow Stem Augers \_\_\_\_\_ TECHNICIAN C. Dorell

## NOTES

## LOG OF BOREHOLE No 104

JOB NAME PROPOSED MILL RACE CONDOMINIUMS

JOHN 85 F 122

LOCATION Water Street North, Cambridge, OntarioBORING DATE 1986.04.22ENGINEER G. MitchellBORING METHOD Continuous Flight Solid Stem AugersDESIGNED BY G. Kelly

SOIL PROFILE			SAMPLES		SHEAR STRENGTH $C_u$		C. TO LIMIT		PLASTIC LIMIT		WATER CONTENT		REMARKS	
DEPTH	DESCRIPTION	ELEVATION	NUMBER	TYPE	BLIND HOLE VALUES	DYNAMIC CONE PENETRATION - STANDARD PENETRATION TEST				WATER CONTENT				REMARKS
						BLOWS / FOOT				WATER CONTENT				
	GROUND ELEVATION 876.1					20	40	60	80					
	FILL: 3.0 in. concrete slab over fine to medium sand, some gravel, trace silt, moist to saturated	875												
			1	SS	6									
		870	2	SS	11									
9.0			3	SS	4									
	SAND: Compact grey coarse sand with little gravel, strong smell of oil, saturated	865	4	SS	12									Borehole became wet after sample 4.
14.0														
	SILT: Dense brown sandy silt, trace gravel, saturated	860	5	SS	49									
16.5	Borehole terminated at 16.5 ft.													Upon completion of drilling, borehole caved at 8.0 ft. with no free water.

NOTES

## LOG OF BOREHOLE No. 125

JOB NAME PROPOSED MILL RACE CONDOMINIUMS

LOCATION Water Street North, Cambridge, Ontario

BORING DATE 1986.04.22

10140 = 5 F . 22

NUMBER 5. "Water..."

BORING METHOD Continuous Flight Solid & Hollow Stem Augers

\*PHONE AND FAX:

SITE PROFILE			SAMPLES			SWF STRATIGRAPHY		LIQUID LIMIT		PLASTIC LIMIT		WATER CONTENT		ADDITIONAL INFORMATION AND REMARKS	
DPTH	DESCRIPTION	DEPTH	SAMPLE NUMBER	TYPE	BORING DEPTH	DYNAMIC CONE PENETRATION STANDARD PENETRATION TEST	FLUIDS FOOT								
	GROUND ELEVATION 877.9														
	FILL: Brown mixture of fine to coarse sand with gravel, moist	875	1	SS	16										
			2	SS	35										
10.0	SAND AND GRAVEL: Very dense brown fine to coarse sand and gravel, damp	870	3	SS	63										
	becoming medium to coarse sand and gravel, saturated		4	SS	50										
14.0		865													
15	SAND: Dense brown silty sand, occasional clayey silt seams, saturated		5	SS	31										
17.0	Borehole terminated at 17.0 ft.														
20															
25															
30															
35															
40															
45															
50															
55															
60															
65															
70															
75															
80															
85															
90															
95															
100															
105															
110															
115															
120															
125															
130															
135															
140															
145															
150															
155															
160															
165															
170															
175															
180															
185															

## NOTES

CHECKED BY \_\_\_\_\_

LOG OF BOREHOLE No. 106

JOB NAME PROPOSED MILL RACE CONDOMINIUMS  
 LOCATION Water Street North, Cambridge, Ontario  
 BORING METHOD Continuous Flight Solid Stem Augers

BORING DATE 1986-04-22  
 ENGINEER G. W. W. W.  
 FIELD NO. 106

SOIL PROFILE		SAMPLES		SHEAR STRENGTH		LIQUID LIMIT		PLASTIC LIMIT		WATER CONTENT	
DEPTH	DESCRIPTION	DEPTH	TYPE	STANDARD PENETRATION TEST	STANDARD PENETRATION TEST	STANDARD PENETRATION TEST	STANDARD PENETRATION TEST	STANDARD PENETRATION TEST	STANDARD PENETRATION TEST	STANDARD PENETRATION TEST	STANDARD PENETRATION TEST
	GROUND ELEVATION 878.2										
	FILL: 2.5 in. concrete slab over brown clayey silt, with some sand and gravel, very moist	875	SS	10							
	SAND: Compact brown and light brown silty sand, occasional silt seams, very moist to saturated	870	SS	14							
		865	SS	19							
			SS	15							
	Borehole terminated at 17.0 ft.										

NOTES

Upon completion of drilling, borehole caved at 12.0 ft. with water level at 11.0 ft.

CHECKED BY gk

MEMBER OF THE ASSOCIATION OF CONSULTING ENGINEERS OF CANADA



## LOG OF BOREHOLE No. 107

JOB NAME PROPOSED MILL RACE CONDOMINIUMS

108 \quad \underline{86 F. 22}

LOCATION Water Street North, Cambridge, Ontario

BORING DATE 1986.04.23

ENGINEER C. M. Moore

BORING METHOD Continuous Flight Hollow Stem AugersTECHNICIAN C. D. Dwyer[illegible]

## NOTES

CHECKED BY

## LOG OF BOREHOLE No. 108

JOB NAME PROPOSED MILL RACE CONDOMINIUMSJOB NO. 86-P-117LOCATION Water Street North, Cambridge, OntarioBORING DATE 1986.04.23ENGINEER G. MitchellBORING METHOD Continuous Flight Solid & Hollow Stem AugersTESTING PLAN See Notes

DEPTH	DESCRIPTION	ELEVATION	NUMBER	TYPE	BLowS/FOOT	SHEAR STRENGTH, C <sub>u</sub>	LIQUID LIMIT	PLASTIC LIMIT	WATER CONTENT	W <sub>L</sub>	W <sub>P</sub>	REMARKS
	GROUND ELEVATION 877.9											
	FILL: 16.0 in. concrete slab over brown mixture of fine to coarse sand and gravel, little silt, moist	875	1	SS	25							
			2	SS	21							
		870	3	SS	18							
10.0			4	SS	11							
13.0	ORGANIC SILT: Stiff dark grey organic silt with sand seams, wet	865	5	SS	11							
16.0	SAND: Compact dark grey fine to medium sand, trace of organics, strong smell of oil, saturated (possible fill)		6	SS	13							
	Borehole terminated at 16.5 ft.											

Borehole becoming wet after sample 4


Upon completion of drilling, water level at 8.0 ft. inside hollow stem augers.

After removing augers borehole caved to 2.0 ft. with no free water.

NOTES

CHECKED BY *gk*

## LOG OF BOREHOLE No. 201

JOB NAME PROPOSED MILL RACE CONDOMINIUMSJOB NO. 25 F. 322LOCATION Water Street North, Cambridge, OntarioBORING DATE 1986.06.22ENGINEER G. McEwenBORING METHOD Continuous Flight Hollow Stem AugersTECHNICIAN C. Kelly

NOTES

CHECKED BY *gh*

## LOG OF BOREHOLE No 202

JOB NAME PROPOSED MILL RACE CONDOMINIUMSDATE SEP 1 1988LOCATION Water Street North, Cambridge, OntarioBORING DATE 1988.06.02ENGINEER G. W. McNameeBORING METHOD Continuous Flight Hollow Stem AugersTECHNICIAN G. W. McNamee

SOIL PROFILE			SAMPLES			SHEAR STRENGTH $C_u$		LIQUID LIMIT $w_L$		PLASTIC LIMIT $w_P$		WATER CONTENT $w$		REMARKS
DEPTH	DESCRIPTION	FIELD ELEVATION	NUMBER	TYPE	DETERMINED BY	DYNAMIC CONE PENETRATION - STANDARD PENETRATION TEST		BLOWS FOOT		WATER CONTENT $w$		WATER CONTENT $w$		
	GROUND ELEVATION 880.1							10	20	30	40	50	60	
	FILL: 2.0 in. of asphaltic concrete over dark brown fine to medium sand and gravel, damp		1	SS	12									
		875	2	SS	4									
			3	SS	8									
9.0	becoming wet with inclusions of coal and brick, strong smell of oil	870	4	SS	9									
12.0														
	ORGANIC SILT: Black organic silt, sand seams, saturated		5	SS	23									
14.0			6	SS	17									
	SAND: Compact to very dense brown fine to medium sand, occasional silt seams, saturated	865												
			7	SS	80									
		860												
			8	SS	34									
25.0		855												
	SAND AND GRAVEL: Very dense brown fine to coarse sand and gravel, saturated													
29.0	Borehole terminated at 29.0 ft. upon meeting refusal to auger	850												
													</	


After sample 6, water level at 14.0 ft.

Upon completion of drilling, borehole caved to 10.3 ft. with no free water

NOTES

CHECKED BY *jk*

## LOG OF BOREHOLE No 003

JOB NAME PROPOSED MILL RACE CONDOMINIUMSLOCATION Water Street North, Cambridge, OntarioBORING DATE 1986.06.03BORING METHOD Continuous Flight Hollow Stem AugersJOB NO. 86-003ENGINEER G. J. H. H.TECHNICAL FILE

NOTES

CHECKED *gh*

JOB NAME PROPOSED MILL RACE CONDUITH.S. 86.7.132ALOCATION Water Street North, Cambridge, OntarioBORING DATE 1986.06.03ENGINEER J. MacdonaldBORING METHOD Continuous Flight Hollow Stem AugersTECHNICIAN D. Kelly

SOIL PROFILE			SAMPLES		SHEAR STRENGTH $C_u$		LIQUID LIMIT $W_L$		PLASTIC LIMIT $W_P$		WATER CONTENT $W$		REMARKS
DEPTH	DESCRIPTION	ELEVATION	NUMBER	TYPE	BLow/VEIN VALUES	DYNAMIC CONE PENETRATION STANDARD PENETRATION TEST	BLows/FOOT	20	40	60	80	WATER CONTENT	
	GROUND ELEVATION 879.4												
8.0	FILL: Dark brown fine to medium sand and gravel, occasional organic inclusions, damp to wet	875	1	SS	3								
			2	SS	1/18 in.								
			3	SS	4								
10.0		870	4	SS	2								
12.0	ORGANIC SILT: Loose dark grey organic silt with occasional sand seams, saturated	865	5	SS	2								
			6	SS	3								
14.0		860	7	SS	6								
16.0	becoming organic sand with shells												
18.0	SAND AND GRAVEL: Very dense brown fine to coarse sand and gravel, saturated	855	8	SS	88/B in.								
20.0													
22.0		850	9	SS	102								
24.0	Borehole terminated at 31.5 ft. upon meeting refusal to auger												
26.0													
28.0													
30.0													
32.0													
34.0													
36.0													
38.0													
40.0													
42.0													
44.0													

After sample 5  
water level at  
11.5 ft.

Upon completion of  
drilling, borehole  
closed to 5.0 ft.  
with no free water


NOTES

CHECKED BY *[Signature]*

PHE 104

MEMBER OF THE ASSOCIATION OF CONSULTING ENGINEERS OF CANADA

## LOG OF BOREHOLE No. 205

JOB NAME PROPOSED MILL RACE CONDOMINIUMSDATE 95.5.1994LOCATION Water Street North, Cambridge, OntarioBORING DATE 1996.06.24SHEET NO. 1BORING METHOD Continuous Flight Hollow Stem AugersDRAWN BY D. Kelly

NOTES

CHECKED BY *gk*

## LOG OF BOREHOLE No. 27

JOB NAME PROPOSED MILL RACE CONDOMINIUM

36 F. 102


LOCATION Water Street North, Cambridge, Ontario

BORING DATE 1988.06.24

DRILLER D. M. Hume

BORING METHOD Continuous Flight Hollow Stem Augers

DRAWN BY D. M. Hume




NOTES

CHECKED BY



## LOG OF BOREHOLE No 207

JOB NAME PROPOSED MILL RACE CONDUITDATE 26.8.2004LOCATION Water Street North, Cambridge, OntarioBORING DATE 1996 Jan 24 & 25BY M. G. G. G.BORING METHOD Continuous Flight Hollow Stem Augers

NOTES

CHECKED BY *JG*



## APPENDIX D

### MISCELLANEOUS FIELD DATA

SINGLE WELL RESPONSE TEST - DATA AND CALCULATIONS  
HYDROSLIP METHOD (1951)

PROJECT NAME: MILL RACE ON THE GRAND PROJECT NUMBER: 2087 CLIENT: C.N.A. Holdings Inc. SUPERVISOR: Ken VanderMeulen	HOLE DESIGNATION: OW14-90 DATE TESTED: FEB. 27/90 TEST TYPE: Falling
--	--


TEST ELEVATION: 268.41 m AMSL TEST DEPTH (H): 4.440 m TEST VOLUME: 1.046 L PL. (H-H <sub>0</sub> ): 0.533 m	WELL RADIUS (r): 0.025 m BOREHOLE RADIUS (R): 0.102 m SCREEN LENGTH (L): 1.220 m TIME LAG (T <sub>0</sub> ): 61 sec
--	--

HYDRAULIC CONDUCTIVITY  $K = (r^2 * \ln(L/R)) / (2 * L * T_0) = 1.0E-03 \text{ cm/sec}$

TIME (actual time)			WATER DEPTH (h)	DISPL. H - h (h)	%DISPL. (H-h)/ (H-H <sub>0</sub> )
days	(HH:MM:SS)	TOTAL (sec.)			
START TIME: 00:00:00					
	00:00:07	7	4.250	0.190	0.357
	00:00:15	15	4.290	0.150	0.282
	00:00:25	25	4.330	0.110	0.206
	00:00:36	36	4.360	0.080	0.150
	00:00:44	44	4.380	0.060	0.113
	00:00:54	54	4.400	0.040	0.075
	00:01:04	64	4.410	0.030	0.056
	00:01:16	76	4.420	0.020	0.038
	00:01:30	90	4.430	0.010	0.019
	00:01:42	102	4.430	0.010	0.019
	00:03:30	210	4.430	0.010	0.019

# SINGLET WELT RESPONSE TEST

0014 90



SINGLE WELL RESPONSE TEST - DATA AND CALCULATIONS  
HVORSLEV METHOD (1951)

TEST NAME: MILL RACE ON THE GRAND TEST NUMBER: 2087 TESTER: C.N.A. Holdings Inc. SUPERVISOR: Lisa Lavallee	HOLE DESIGNATION: OW15-90 DATE TESTED: Feb. 27/90 TEST TYPE: Falling
---	--

ELEVATION: 268.54 m AMSL TEST DEPTH (H): 4.490 m TEST VOLUME: 1.046 L PL. (H-Ho): 0.533 m	WELL RADIUS (r): 0.025 m BOREHOLE RADIUS (R): 0.102 m SCREEN LENGTH (L): 1.220 m TIME LAG (To): 1055 secs
--	--


  

HYDRAULIC CONDUCTIVITY  $K = (r^2 * \ln(L/R)) / (2 * L * To) = 6.0E-05$  cm/sec

TIME (actual time)			WATER DEPTH (h)	DISPL. H - h	%DISPL. (H-h)/ (H-Ho)
days	(HH:MM:SS)	TOTAL (sec.)			
START TIME:	00:00:00				
	00:00:11	11	4.150	0.340	0.638
	00:00:17	17	4.160	0.330	0.619
	00:00:31	31	4.165	0.325	0.610
	00:00:40	40	4.170	0.320	0.601
	00:00:55	55	4.180	0.310	0.582
	00:01:17	77	4.190	0.300	0.563
	00:01:39	99	4.200	0.290	0.544
	00:02:00	120	4.210	0.280	0.526
	00:03:00	180	4.230	0.260	0.488
	00:04:00	240	4.250	0.240	0.451
	00:05:00	300	4.265	0.225	0.422
	00:06:00	360	4.280	0.210	0.394
	00:07:00	420	4.290	0.200	0.375
	00:08:00	480	4.305	0.185	0.347
	00:09:00	540	4.315	0.175	0.329
	00:10:00	600	4.327	0.163	0.306
	00:11:00	660	4.335	0.155	0.291
	00:12:00	720	4.345	0.145	0.272
	00:13:30	810	4.355	0.135	0.253
	00:15:00	900	4.368	0.122	0.229
	00:16:30	990	4.378	0.112	0.210
	00:18:00	1080	4.383	0.107	0.201
	00:19:30	1170	4.393	0.097	0.182
	00:21:30	1290	4.400	0.090	0.169
	00:23:30	1410	4.410	0.080	0.150
	00:25:30	1530	4.420	0.070	0.131
	00:27:30	1650	4.425	0.065	0.122
	00:29:30	1770	4.430	0.060	0.113
	00:31:30	1890	4.437	0.053	0.099
	00:34:30	2070	4.442	0.048	0.090
	00:36:30	2190	4.450	0.040	0.075
	00:39:00	2340	4.452	0.038	0.071
	00:41:30	2490	4.455	0.035	0.066
	00:44:30	2670	4.460	0.030	0.056
	00:47:30	2850	4.465	0.025	0.047
	00:52:30	3150	4.475	0.015	0.028
	00:57:30	3450	4.482	0.008	0.015
	01:02:30	3750	4.482	0.008	0.015
	01:07:30	4050	4.482	0.008	0.015


# SINGLE WELL RESPONSE TEST

Example 1



PROJECT NO. 2683  
 PROJECT NAME Cambridge  
 LOCATION 6413 E.  
 DATE .. April 25/83

SOIL DESCRIPTION .....  
 Depth 20.22 ft .....  
 .....  
 TESTED BY .....






PROJECT NO. .... 2084  
PROJECT NAME .... Cambridge  
LOCATION .... 6411-87  
DATE .... 05/01/87

GRAIN SIZE ANALYSIS  
DATA SHEET

SOIL DESCRIPTION .....  
Depth 15 ft  
TESTED BY .....





## APPENDIX E

### ANALYTICAL REPORTS

DATE: March 30, 1987

CLIENT  
ORDER # 2087

Attention: Ms. K. Kaufman

REPORT # NL-2402

RE Analysis of Soil Samples for Naphthalene and Benzo(a)Pyrene

Ms. Kaufman,

Two (2) soil samples, received March 19, 1987, were analysed for naphthalene and benzo(a)pyrene indicator PAH compounds by solvent extraction and gas chromatography with flame ionization detection. Results and detection limits are shown in the table below.

Table - Concentration of Indicator PAH Compounds in Soil Samples (ug/g)

<u>Sample</u>	<u>Naphthalene</u>	<u>Benzo(a) Pyrene</u>
BF 0016	2.38	<0.5
BF 0025	<0.05	<0.05

Chromatograms will be kept on file.

Sincerely,

**NOVALAB LIMITED**



B.E. Crowley, B.Sc.



Approved by J.D. Fenwick, Ph.D., P. Chem.

BEC/hl



DATE May 19, 1987

CLIENT ORDER # 2087

REPORT # NL-2535

RE Analysis of Soil for PAH  
Analysis of Leachate for PAH

Ms. Kaufman,

Ten (10) soil samples were received April 28, 1987. Two (2) of these samples were analysed for polycyclic aromatic hydrocarbons by EPA method 625. All ten (10) soil samples were leached, according to the leaching procedure of Environment Quebec, and the resulting leachate was analysed also for PAH by EPA method 625.

Results and detection limits are shown in the appended tables.

Chromatograms will be kept on file. Results of gc/ms analyses are not corrected for recovery.

Sincerely,

**NOVALAB LIMITED**

*B.E. Crowley*  
B.E. Crowley, B.Sc.

*J.D. Fenwick*  
Approved by J.D. Fenwick, Ph.D., P.Chem.

BEC/hl  
encl.



CONCENTRATION OF PAH IN SOIL SAMPLES  
ug/g

COMPOUND	2087		2087		Blank	MDL
	#1	MDL	#2	MDL		
ACENAPHTHENE	2230	30	-	3	-	0.3
ACENAPHTHYLENE	160	30	89.2	3	-	0.3
ANTHRACENE	1250	30	55.8	3	-	0.3
BENZ(A)ANTHRACENE	400	30	11.3	3	-	0.3
CHRYSENE	640	30	23.7	3	-	0.3
BENZO(B)FLUORANTHENE						
BENZO(K)FLUORANTHENE	420	50	TR	5		0.5
BENZO(A)PYRENE	530	50	TR	5	-	0.5
BENZO(GHI)PERYLENE	330	150	-	15	-	1.5
DIBENZ(A,H)ANTHRACENE	-	150	-	15	-	1.5
FLUORANTHENE	2400	30	112	3	-	0.3
FLUDRENE	780	30	16.1	3	-	0.3
INDENO(1,2,3-cd)PYRENE	220	150	-	15	-	1.5
NAPHTHALENE	10300	30	180	3	-	0.3
PHENANTHRENE	5250	30	188	3	-	0.3
PYRENE	510	30	24.8	3	-	0.3

MDL = METHOD DETECTION LIMIT

Total concentration of benzo(b)- and benzo(k)fluoroanthene is shown in the row for benzo(b)fluoranthene.

RECOVERY OF SURROGATE STANDARDS  
(%)

COMPOUND	2087	2087	Blank
	#1	#2	
D8-NAPHTHALENE			55.6
D10-ANTHRACENE			57.2
D10-FLUORANTHENE			60.8
D12-PERYLENE			100

CONCENTRATION OF PAH IN LEACHATE SAMPLES  
ug/L

COMPOUND	2087 #1	2087 #5	MDL	2087 #2	MDL	2087 #3	2087 #4	2087 #6	2087 #7	MDL
ACENAPHTHENE	47.7	3.4	1	50.4	0.2	-	27.1	0.5	0.3	0.1
ACENAPHTHYLENE	283	355	1	2.7	0.2	-	0.4	-	-	0.1
ANTHRACENE	6.2	21	1	0.5	0.2	-	1	-	-	0.1
BENZ(A)ANTHRACENE+CHRYSENE	-	-	1	-	0.2	-	-	-	-	0.1
BENZO(B)FLUORANTHENE										0.1
BENZO(K)FLUORANTHENE	-	-	2	-	0.2	-	-	-	-	0.1
BENZO(A)PYRENE	-	-	2	-	0.2	-	-	-	-	0.1
BENZO(GHI)PERYLENE	-	-	5	-	0.4	-	-	-	-	0.2
DIBENZ(A,H)ANTHRACENE	-	-	5	-	0.4	-	-	-	-	0.2
FLUORANTHENE	3.5	5.6	1	-	0.2	-	0.2	-	-	0.1
FLUORENE	82	82	1	6.7	0.2	-	5.1	-	0.2	0.1
INDENO(1,2,3-cd)PYRENE	-	-	5	-	0.4	-	-	-	-	0.2
NAPHTHALENE	10550	777	1	240	0.2	-	0.3	1.4	1.6	0.1
PHENANTHRENE	117	160	1	6.6	0.2	-	6	-	0.4	0.1
PYRENE	5.7	6.1	1	-	0.2	-	0.5	-	-	0.1

MDL = METHOD DETECTION LIMIT

Total concentration of benzo(b)- and benzo(k)fluoranthene is shown  
in the row for benzo(k)fluoranthene.

RECOVERY OF SURROGATE STANDARDS  
(%)

COMPOUND	2087 #1	2087 #5	2087 #2	2087 #3	2087 #4	2087 #6	2087 #7
DB-NAPHTHALENE	94.4	63.5	52.2	62.2	50.6	63.5	56.7
D10-ANTHRACENE	81.4	63	87.4	76.7	85.7	77.9	83.2
D10-FLUORANTHENE	74.1	63.6	90.9	75.6	85	78.8	82.9
D12-PERYLENE	100	100	83.5	46.6	82.4	44.9	81.3

CONCENTRATION OF PAH IN LEACHATE SAMPLES

ug/L

COMPOUND	2087 #8	2087 #9	2087 #10	Leach. Blank	Lab Blank	MDL
ACENAPHTHENE	-	-	-	-	-	0.1
ACENAPHTHYLENE	-	-	-	-	-	0.1
ANTHRACENE	-	-	-	-	-	0.1
BENZ(A)ANTHRACENE + CHRYSENE	-	-	-	-	-	0.1
BENZO(B)FLUORANTHENE	-	-	-	-	-	0.1
BENZO(K)FLUORANTHENE	-	-	-	-	-	0.1
BENZO(A)PYRENE	-	-	-	-	-	0.1
BENZO(GH)PERYLENE	-	-	-	-	-	0.2
DIBENZ(A,H)ANTHRACENE	-	-	-	-	-	0.2
FLUORANTHENE	-	-	-	-	-	0.1
FLUORENE	-	-	-	-	-	0.1
INDENO(1,2,3-cd)PYRENE	-	-	-	-	-	0.2
NAPHTHALENE	-	-	-	-	-	0.1
PHENANTHRENE	-	0.2	-	-	-	0.1
PYRENE	-	-	-	-	-	0.1

MDL = METHOD DETECTION LIMIT

Total concentration of benzo(b)- and benzo(k)fluoroanthene is shown in the row for benzo(k)fluoranthene.

RECOVERY OF SURROGATE STANDARDS  
(%)

COMPOUND	2087 #8	2087 #9	2087 #10	Leach. Blank	Lab Blank
D8-NAPHTHALENE	47.6	67	87.9	72.1	68.6
D10-ANTHRACENE	71.2	74.5	87.4	75.7	86.8
D10-FLUORANTHENE	80.4	82	90.4	93.2	87.1
D12-PERYLENE	87.3	45.5	59.1	44.5	92.9



# CHAIN OF CUSTODY RECORD

PROJECT NO.

2087

PROJECT NAME:

MELL RACE CONDOMINIUMS

SAMPLER'S SIGNATURE Peter Hayes  
(SIGN)

SAMPLE  
TYPE

NO OF  
CONTAINERS

REMARKS

SEQ.  
NO.

SAMPLE  
NO.

DATE

TIME

SAMPLE LOCATION

#1  
#2  
#3  
#4  
#5  
#6  
#7  
#8  
#9  
#10

April 1982

Soil

1  
1  
1  
1  
1  
1  
1  
1  
1  
1

TOTAL # LEACH P.H.  
TOTAL # LEACH P.H.  
LEACH P.H.

TOTAL NO. OF CONTAINERS

10

RELINQUISHED BY:

1 Peter Hayes  
(SIGN)

DATE/TIME

April 1982

RECEIVED BY:

2 Peter Hayes  
(SIGN)

RELINQUISHED BY:

2 Peter Hayes  
(SIGN)

DATE/TIME

April 1982

RECEIVED BY:

3 Peter Hayes  
(SIGN)

RELINQUISHED BY:

3 Peter Hayes  
(SIGN)

DATE/TIME

April 1982

RECEIVED BY:

4 Peter Hayes  
(SIGN)

RELINQUISHED BY:

4 Peter Hayes  
(SIGN)

DATE/TIME

April 1982

RECEIVED BY:

5 Peter Hayes  
(SIGN)

METHOD OF SHIPMENT:

SHIPPED BY:

RECEIVED FOR LABORATORY BY:

DATE/TIME

(SIGN) Peter Hayes

22/4

CONDITION OF SEAL UPON RECEIPT:

GENERAL CONDITION OF COOLER:

COOLER OPENED BY:

(SIGN) Peter Hayes

DATE/TIME

22/4

- WHITE - RECEIVING LABORATORY COPY
- YELLOW - SHIPPER'S COPY
- PINK - CRA LABORATORY COPY
- GOLDEN ROD - CRA OFFICE COPY

002046

DATE: May 19, 1987

CLIENT  
ORDER # 2087

REPORT # NL-2526

---

RE: Analysis of Water for PAH and Volatile Priority Pollutants

Ms. Kaufman,

One (1) sample of water, received May 1, 1987, was analysed for volatile priority pollutants by EPA method 624. One (1) sample of water, also received May 1, 1987, was analysed for polycyclic aromatic hydrocarbons by EPA method 625.

Results and detection limits are shown in the appended tables.

Chromatograms will be kept on file. Results of gc/ms are not corrected for recovery.

Sincerely,

**NOVALAB LIMITED**



B.E. Crowley, B.Sc.



Approved by J.D. Fenwick, Ph.D., P.Chem.

BEC/hl



CONCENTRATION OF VOLATILE PRIORITY POLLUTANTS IN WATER  
ug/L

COMPOUND	W-042987 PH-001	MDL
BENZENE	8940	1000
BROMODICHLOROMETHANE	-	100
BROMOFORM	-	500
BROMOMETHANE	-	100
CARBON TETRACHLORIDE	-	500
CHLOROBENZENE	-	100
CHLOROETHANE	-	100
2-CHLOROETHYL VINYL ETHER	-	5000
CHLOROFORM	-	100
CHLOROMETHANE	-	100
DIBROMOCHLOROMETHANE	-	100
1,2-DICHLOROBENZENE	-	150
1,3-DICHLOROBENZENE	-	-
1,4-DICHLOROBENZENE	-	150
1,1-DICHLOROETHYLENE	-	100
1,1-DICHLOROETHANE	-	100
1,2-DICHLOROETHANE	-	100
TRANS-1,2-DICHLOROETHYLENE	-	100
DICHLOROMETHANE	-	5000
1,2-DICHLOROPROPANE	-	100
CIS-1,3-DICHLOROPROPENE	-	250
TRANS-1,3-DICHLOROPROPENE	-	100
ETHYLBENZENE	5000	50
A-METHYLSTYRENE	130	50
MESITYLENE	740	50
1,1,2,2-TETRACHLOROETHANE	-	1000
TETRACHLOROETHYLENE	-	100
TOLUENE	4190	500
1,1,1-TRICHLOROETHANE	-	100
1,1,2-TRICHLOROETHANE	-	250
TRICHLOROETHYLENE	-	100
TRICHLOROFLUOROMETHANE	-	500
M+P-XYLENE	1410	50
O-XYLENE	780	50
VINYL CHLORIDE	-	250
OTHER AROMATIC COMPOUNDS	-	50

MDL = METHOD DETECTION LIMITS

OTHER AROMATIC COMPOUNDS = Total concentration of tri- and tetramethylbenzenes  
using the response factor of mesitylene.

Total concentration of 1,3- and 1,4-dichlorobenzene is shown in the  
row for 1,4-dichlorobenzene.

CONCENTRATION OF PAH IN WATER SAMPLES  
ug/L

COMPOUND	W-042987	Lab	MDL
	PH-001	Blank	
ACENAPHTHENE	112	-	10
ACENAPHTHYLENE	19.3	-	10
ANTHRACENE	126	-	10
BENZ(A)ANTHRACENE	33.7	-	10
CHRYSENE	52.5	-	10
BENZO(B)FLUDRANTHENE			
BENZO(K)FLUDRANTHENE	41	-	20
BENZO(A)PYRENE	54.6	-	20
BENZO(GHI)PERYLENE	TR	-	50
DIBENZ(A,H)ANTHRACENE	-	-	50
FLUDRANTHENE	239	-	10
FLUDRENE	303	-	10
INDENO(1,2,3-cd)PYRENE	TR	-	50
NAPHTHALENE	8788	-	10
PHENANTHRENE	805	-	10
PYRENE	267	-	10

MDL = METHOD DETECTION LIMIT

Total concentration of benzo(b)- and benzo(k)fluoroanthene is shown in the row for benzo(k)fluoranthene.

RECOVERY OF SURROGATE STANDARDS  
(1)

COMPOUND	W-042987	Lab
	PH-001	Blank
DB-NAPHTHALENE		62.8
D10-ANTHRACENE		68.8
D10-FLUDRANTHENE		78.3
D12-PERYLENE		51.4

# CHAIN OF CUSTODY RECORD

PROJECT NO.

2007

PROJECT NAME:

MILL RACE CON.

SAMPLER'S SIGNATURE

(SIGN)

SAMPLE  
TYPE

NO.  
OF  
CONTAINERS

REMARKS

SEQ. SAMPLE DATE TIME SAMPLE LOCATION

001 April 29

water

2

PAH, UCC

1 TRIP PLANK

TOTAL NO. OF CONTAINERS

2

RELINQUISHED BY:

1

(SIGN)

DATE/TIME

April 30, 1987

RECEIVED BY:

2

(SIGN)

RELINQUISHED BY:

2

(SIGN)

DATE/TIME

1-10-7, 11:00 am

RECEIVED BY:

3

(SIGN)

RELINQUISHED BY:

3

(SIGN)

DATE/TIME

1

RECEIVED BY:

4

(SIGN)

RELINQUISHED BY:

4

(SIGN)

DATE/TIME

1

RECEIVED BY:

5

(SIGN)

METHOD OF SHIPMENT:

SHIPPED BY:

RECEIVED FOR LABORATORY BY:

(SIGN)

DATE/TIME

5/1/87

CONDITION OF SEAL UPON RECEIPT:

GENERAL CONDITION OF COOLER:

COOLER OPENED BY:

(SIGN)

DATE/TIME

5/1/87

WHITE - RECEIVING LABORATORY COPY  
YELLOW - SHIPPER'S COPY  
PINK - CRA LABORATORY COPY  
GOLDEN ROD - CRA OFFICE COPY

00-207

DATE Jan. 27, 1989

CLIENT  
ORDER # 2087

REPORT # NL-4496

Attention: Ms. D. Hayes

RE Analysis of Water and Sediment for PAH - Project 2087

Ms. Hayes,

Two (2) water samples and three (3) sediment samples, received December 19, 1988, were analysed for polycyclic aromatic hydrocarbons by gc/ms equipped with a mass selective detector operated in the single ion monitoring mode (EPA method 625).

The water samples, identified as 2087 W-1 and 2087 W-2, were extracted on December 21, 1988 and analysed by gc/ms on December 24, 1988. The sediment samples, identified as 2087 S-1, 2087 S-2, and 2087 S-3, were extracted on December 23, 1988 and analysed by gc/ms on January 7, 1989.

The water samples contained only a very small amount of fine sediment, and this was allowed to settle out completely before the water for analysis was taken. The sediment samples were allowed to settle for four (4) days before the water portion was removed and the resulting sediment analysed (as discussed with Mr. Brian Crowley). The removed water was retained. One sample was also analysed in duplicate. Results and detection limits are shown in the attached Tables.

Chromatograms will be kept on file. Results are not corrected for recovery.

Sincerely,

NOVALAB LIMITED

*L.W. Tang*

L.W. Tang, B.Sc. for J.D. Fenwick, Ph.D., P.Chem.

LWT/hl  
encl.



CONCENTRATION OF POLYCYCLIC AROMATIC HYDROCARBONS IN SOIL

ug/g

COMPOUND	2087		DUPL.		BLANK	MOL
	S-1	S-2	S-1	S-3		
ACENAPHTHENE	-	0.02	-	0.02	-	0.02
ACENAPHTYLENE	-	-	-	-	-	0.02
ANTHRACENE	0.03	0.03	0.06	0.1	-	0.02
BENZO(A)ANTHRACENE	0.3	0.1	0.3	0.2	-	0.02
BENZO(B)FLUORANTHENE]						
BENZO(K)FLUORANTHENE]	1.0	0.4	0.9	1.1	-	0.02
BENZO(A)PYRENE	0.5	0.1	0.4	0.7	-	0.02
BENZO(GH)PERYLENE	0.2	0.1	0.3	0.4	-	0.04
CHRYSENE	0.6	0.1	0.5	0.5	-	0.02
DIBENZ(A,H)ANTHRACENE	0.09	TR	0.1	0.1	-	0.04
FLUORANTHENE	0.6	0.4	0.6	0.9	-	0.02
FLUORENE	-	-	-	0.04	-	0.02
INDENO(1,2,3-CD)PYRENE	0.2	0.08	0.2	0.3	-	0.04
NAPHTHALENE	-	-	-	-	-	0.02
PERMANTHRENE	0.3	0.2	0.2	0.5	-	0.02
PYRENE	0.6	0.4	0.6	0.8	-	0.02

MOL = METHOD DETECTION LIMIT

TR = TRACE

Total concentration of benzo(b)- and benzo(k)fluoranthene is shown in the row for benzo(k)fluoranthene.

RECOVERY OF SURROGATE STANDARDS  
(%)

COMPOUND	2087		DUPL.		BLANK	
	S-1	S-2	S-1	S-3		
DB-NAPHTHALENE	36.5	31.2	33.8	34.9	30.1	
D10-ANTHRACENE	64.6	66.8	68.6	70.5	51.5	
D10-FLUORANTHENE	79	75.8	77.4	78.4	74.3	
D12-PERYLENE	96.6	97.2	99.9	97.4	99.2	

CONCENTRATION OF POLYCYCLIC AROMATIC HYDROCARBONS IN WATER

ug/L

COMPOUND	2087	2087	BLANK	MDL
	W-1	W-2		
ACENAPHTHENE	-	-	-	0.05
ACENAPHTYLENE	-	-	-	0.05
ANTHRACENE	-	-	-	0.05
BENZ(A)ANTHRACENE	-	-	-	0.05
BENZO(B)FLUORANTHENE	-	-	-	0.05
BENZO(K)FLUORANTHENE	0.06	-	-	0.05
BENZO(A)PYRENE	-	-	-	0.05
BENZO(GHI)PERYLENE	-	-	-	0.1
CHRYSENE	-	-	-	0.05
DIBENZ(A,B)ANTHRACENE	-	-	-	0.1
FLUORANTHENE	0.06	-	-	0.05
FLUORENE	-	-	-	0.05
INDENO(1,2,3-CD)PYRENE	-	-	-	0.1
NAPHTHALENE	-	-	-	0.05
PHENANTHRENE	-	-	-	0.05
PYRENE	-	-	-	0.05

MDL = METHOD DETECTION LIMIT

Total concentration of benzo(b)- and benzo(k)fluoranthene is shown in the row for benzo(k)fluoranthene.

RECOVERY OF SURROGATE STANDARDS  
(%)

COMPOUND	2087	2087	BLANK
	W-1	W-2	
D8-NAPHTHALENE	54	41.6	32.4
D10-ANTHRACENE	59.4	57.4	54.3
D10-FLUORANTHENE	67.9	70.1	66.8
D12-PERYLENE	80.4	85.5	83.5



Doc 005674

WHITE - CRA OFFICE COPY  
YELLOW - RECEIVING LABORATORY COPY  
PINK - CRA LABORATORY COPY  
GOLDEN ROD - SHIPPERS

Page 1  
Received: 02/13/90

Bear Analytical REPORT  
03.05/90 13:03:33

Work Order # 90-02-108

MAR 1 1990

REPORT Conestoga-Rovers & Associates PREPARED Bear Analytical Services  
TO 551 Gold Drive BY 14 Abacus Road  
Waterloo, Ontario Brampton, Ontario  
N2L 1G2 L7T 5B7  
ATTN Frank J. LeBeau ATTN Chester Labortia  
PHONE 416-458-4044 CONTACT V. McMillan  
CLIENT CRA SAMPLES 1  
COMPANY Conestoga-Rovers & Associates  
FACILITY \_\_\_\_\_  
Bear Analytical Services hereby disclaims any and all  
liability related to anomalous data arising from normal  
analytical and/or sampling protocols. Should further  
information be required, please contact the Supervisor.  
WORK TO Protect CIE Millage  
TAKEN 02.12.90  
TRANS \_\_\_\_\_  
TYPE Spot  
P. I. # \_\_\_\_\_  
INVOICE under separate cover

SAMPLE IDENTIFICATION

TEST CODES and NAMES used on this report

01 S-0087-KMV-001	HEXCRS Hexavalent Chromium
02 S-0087-KMV-005	S01 ZN Zinc
	S02 CD Cadmium
	S04 CO Cobalt
	S08 CU Copper
	S07 PB Lead
	S08 CR Chromium
	S09 NI Nickel
	S10 BE Beryllium
	S11 MO Molybdenum
	S13 V Vanadium
	S16 BA Barium
	S20 HG Mercury
	S21 AS Arsenic
	S22 SE Selenium
	S23 AG Silver
	S25 SB Antimony

2087  
MONITORING DATA

14 Abacus Road  
Brampton, Ontario  
Canada L6T 5B7

Tel: (416) 458-4044  
Fax: (416) 458-7303

Conestoga-Powers & Associates  
651 Colby Drive  
Waterloo, Ontario  
N2V 1G2  
Attn: Graham Chevreau

Date Received: 02/13/90  
Date Reported: 02/05/90  
Work Order: 90-02-109  
Category:

Work ID: Project 0387 Millrace  
P.O. #

Test	Units	S-2087-KMV-001	S-2087-KMV-005
Hexavalent Chromium		0.179	0.28
	ug/g		
Zinc		56	89/92
	ug/g		
Cadmium		0.10	0.30/0.40
	ug/g		
Cobalt		2.5	2.5/2.5
	ug/g		
Copper		13.5	14.5/12.5
	ug/g		
Lead		5.0	18.0/20.0
	ug/g		
Chromium		17	23/24
	ug/g		
Nickel		9	12 / 13
	ug/g		
Beryllium		<1	<1/<2
	ug/g		
Molybdenum		4	4 / 4
	ug/g		
Vanadium		14	24/27
	ug/g		
Barium		17	38/42
	ug/g		
Mercury		<0.02	<0.02
	ug/g		
Arsenic		<0.5	3.0/3
	ug/g		
Selenium		<0.5	<0.5/<1
	ug/g		
Silver		<0.5	<0.5/<1
	ug/g		
Antimony		<1	<1/<2
	ug/g		

Certified By:



Page 2 Beak Analytical REPORT  
Received: 02/13/90 Test Methodology

Work Order # 90-02-108

TEST CODE HEXCBS NAME Hexavalent Chromium

Diphenylcarbazide - Colorimetric

Reference Ontario Ministry of the Environment Handbook of Analytical Methods  
for Environmental Samples, 1983, No. CG1.

W.O. #90.02.108

QA/QC REPORT

PARAMETER	EXTRACTED DATE	ANALYSED DATE	ANALYTICAL BLANK	QA/QC
Cadmium	February 14, 1990	February 20, 1990	<0.0001 mg/L	BCSS-1  True Value: 0.25 Analyzed Value: 0.24
Cobalt	Not Applicable	February 26, 1990	<0.001 mg/L	BCSS-1  True Value: 11.4 Analyzed Value: 10.4
Copper	Not Applicable	February 20, 1990	-	WP 386  True Value: 100 Analyzed Value: 107
Lead	Not Applicable	February 21, 1990	<0.001 mg/L	WP386  True Value: 22.7 Analyzed Value: 21.2
Chromium	Not Applicable	February 28, 1990	<0.01 mg/L	WP386  True Value: 123 Analyzed Value: 58.5
Mercury	February 19, 1990	February 20, 1990	<0.05 ug/L	WP386  True Value: 0.12 Analyzed Value: 0.10
Arsenic	February 21, 1990	February 21, 1990	<1 ug/L	BCSS-1  True Value: 11.1 Analyzed Value: 9.5
Selenium	February 21, 1990	February 21, 1990	<1 ug/L	BCSS-1  True Value: 0.43 Analyzed Value: <0.5
Antimony	February 20, 1990	February 20, 1990	<2 ug/L	BCSS-1  True Value: 0.59 Analyzed Value: <1

W.O. #90.02.108

QA/QC REPORT (CONTINUED)

PARAMETER	EXTRACTED DATE	ANALYSED DATE	ANALYTICAL BLANK	QA/QC
Zinc	Not Applicable	February 19, 1990	0.02 mg/L	BCSS-1 True Value: 119 Analyzed Value: 115
Nickel	Not Applicable	February 19, 1990	<0.01 mg/L	BCSS-1 True Value: 55.3 Analyzed Value: 54.1
Beryllium	Not Applicable	February 21, 1990	<0.01 mg/L	BCSS-1 True Value: 1.3 Analyzed Value: 1.6
Molybdenum	Not Applicable	February 21, 1990	<0.01 mg/L	BCSS-1 True Value: - Analyzed Value: 5.4
Vanadium	Not Applicable	February 21, 1990	<0.01 mg/L	BCSS-1 True Value: 93.4 Analyzed Value: 49.8
Barium	Not Applicable	February 21, 1990	<0.01 mg/L	BCSS-1 True Value: - Analyzed Value: 56.6
Silver	Not Applicable	February 21, 1990	<0.01 mg/L	Municipal Sludge True Value: 80.6 Analyzed Value: 70.0

W.O. 890.02.108

METHODS

Cadmium	Graphite Furnace
Cobalt	Graphite Furnace
Copper	Graphite Furnace
Lead	Graphite Furnace
Chromium	DCP
Mercury	Cold Vapour - Flameless Atomic Absorption (MOE 1983)
Arsenic	Hydride Generation
Selenium	Hydride Generation
Antimony	Graphite Furnace
Zinc	DCP
Nickel	DCP
Beryllium	DCP
Molybdenum	DCP
Vanadium	DCP
Barium	DCP
Silver	Graphite Furnace

Note: Beckman Instruments Inc.  
Direct Current Plasma (DCP) Optional Emission Spectrometric Method for Trace Elemental  
Analysis of Water and Wastes. Method AES 0029, 1984

MAR 13 1990

TEL (514) 636-6218 631-1838  
FAX (514) 631-9814

DATE: March 7, 1990

CLIENT  
ORDER # 2087

REPORT # NL-6713

Attention: Mr. G. Chevreau

RE Analysis of Soil Samples - Project Millrace

Sir,

Two (2) soil samples, received February 13, 1990, were extracted February 27, 1990 and analysed for polycyclic aromatic hydrocarbons by gas chromatography with flame ionization detection. Results are shown in the attached Table.

Chromatograms will be kept on file.

Regards,

**NOVALAB LIMITED**


*E.E. Keirstead*

E.E. Keirstead, B.Sc., Dipl.

*J.D. Fenwick*

Approved by J.D. Fenwick, Ph.D., P.Chem.

EEK/hl  
encl.





CONCENTRATION OF POLYCYCLIC AROMATIC HYDROCARBONS IN SOIL

ug/g  
7.26 1.67

COMPOUND	S-2087 RMV-002	S-2087 RMV-006
NAPHTHALENE	< 0.05	0.42
ACENAPHTYLENE	< 0.05	0.05
ACENAPHTHENE	< 0.05	0.69
FLUORENE	< 0.05	0.32
PERMANTHRENE	< 0.05	1.2
ANTHRACENE	< 0.05	0.35
FLUORANTHENE	< 0.05	0.53
PYRENE	< 0.05	0.75
BENZ(A)ANTHRACENE	< 0.05	0.19
CHRISENE	< 0.05	0.21
BENZO(B)FLUORANTHENE]		
BENZO(K)FLUORANTHENE]	< 0.12	0.24
BENZO(A)PYRENE	< 0.1	0.2
INDENO(1,2,3-CD)PYRENE]		
DIBENZ(A,H)ANTHRACENE]	< 0.25	< 0.25
BENZO(G,H,I)PERYLENE	< 0.2	< 0.2

MDL = METHOD DETECTION LIMIT

< = LESS THAN

Total concentration of benzo(b)- and benzo(k)fluoranthene is shown in the row for benzo(k)fluoranthene.

Total concentration of indeno(1,2,3-cd)pyrene and dibenz(a,h)anthracene is shown in the row for dibenz(a,h)anthracene.

# CHAIN OF CUSTODY RECORD

PROJECT NO:  
2087

PROJECT NAME:  
MILLRACE

SAMPLER'S SIGNATURE

(SIGN)

SAMPLE  
TYPE

NO  
OF  
CONTAINERS

REMARKS

SEQ.  
NO

SAMPLE NO

DATE

TIME

SAMPLE LOCATOIN

C-2087-KMU-002

02-08-90

SOIL

1

PAH

C-2087-KMU-006

02-09-90

SOIL

1

PAH

TOTAL NUMBER OF CONTAINERS

2

ANTICIPATED CHEMICAL HAZARDS:

PNA, TPH

RELINQUISHED BY:

1

(SIGN)

DATE/TIME

RECEIVED BY:

2

S. Dugway  
(SIGN)

RELINQUISHED BY:

2

(SIGN)

DATE/TIME

RECEIVED BY:

3

(SIGN)

RELINQUISHED BY:

3

(SIGN)

DATE/TIME

RECEIVED BY:

4

(SIGN)

ADDITIONAL SIGNATURE  
SHEET REQUIRED

☐

METHOD OF SHIPMENT:

SHIPPED BY:

RECEIVED FOR LABORATORY BY:

DATE/TIME

(SIGN)

CONDITION OF SEAL UPON RECEIPT:

GENERAL CONDITION OF COOLER:

COOLER OPENED BY:

DATE/TIME

(SIGN)

WHITE  
YELLOW  
PINK  
GOLDEN ROD

- CRA OFFICE COPY  
- RECEIVING LABORATORY COPY  
- CRA LABORATORY COPY  
- SHIPPERS

10 009311

TEL (514) 636-6218 631-1838  
FAX (514) 631-9814

Rec'd CRA

APR 02 1990

DATE: March 28, 1990

CLIENT  
ORDER # 2087

REPORT # NL-6896

Attention: Mr. G. Chevreau

RE: Analysis of Water Samples - Project Mill Race


Sir,

Four (4) water samples were received on February 26, 1990. Two (2) water samples were extracted on February 28, 1990 and analysed for polycyclic aromatic hydrocarbons by gas chromatography with flame ionization detection and the other two (2) samples were extracted on February 26, 1990 and analysed for volatile priority pollutants by gc/ms. Results and detection limits are shown in the attached Tables.

All data will remain on file.

Sincerely,

NOVALAB LIMITED



B.E. Crowley, B.Sc.



Approved by J.D. Fenwick, Ph.D., P.Chem.

BEC/hl  
encl.



CONCENTRATION OF VOLATILE PRIORITY POLLUTANTS IN WATER  
ug/L

COMPOUND	W-2067 KMV-001	W-2087 KMV-005	BLANK	MDL
BENZENE	ND	ND	ND	1
BROMODICHLOROMETHANE	ND	ND	ND	1
BROMOFORM	ND	ND	ND	2
BROMOMETHANE	ND	ND	ND	10
CARBON TETRACHLORIDE	ND	ND	ND	2
CHLOROBENZENE	ND	ND	ND	1
CHLOROETHANE	ND	ND	ND	10
2-CHLOROETHYL VINYL ETHER	ND	ND	ND	10
CHLOROFORM	4.3	ND	ND	1
CHLOROMETHANE	ND	ND	ND	10
DIBROMOCHLOROMETHANE	ND	ND	ND	1
DIBROMOETHANE	ND	ND	ND	4
1,2-DICHLOROBENZENE	ND	ND	ND	1
1,3-DICHLOROBENZENE	ND	ND	ND	1
1,4-DICHLOROBENZENE	ND	ND	ND	1
1,1-DICHLOROETHYLENE	ND	ND	ND	1
1,1-DICHLOROETHANE	ND	ND	ND	1
1,2-DICHLOROETHANE	ND	ND	ND	2
TRANS-1,2-DICHLOROETHYLENE	ND	ND	ND	1
DICHLOROMETHANE	ND	ND	ND	5
1,2-DICHLOROPROPANE	ND	ND	ND	1
CIS-1,3-DICHLOROPROPENE	ND	ND	ND	1
TRANS-1,3-DICHLOROPROPENE	ND	ND	ND	1
ETHYLBENZENE	1.1	ND	ND	1
A-METHYLSTYRENE	ND	ND	ND	1
METHYLSTYRENE ISOMERS	ND	ND	ND	1
MESITYLENE	ND	ND	ND	1
STYRENE	ND	ND	ND	2
1,1,2,2-TETRACHLOROETHANE	ND	ND	ND	2
TETRACHLOROETHYLENE	ND	ND	ND	1
TOLUENE	ND	ND	ND	2
1,1,1-TRICHLOROETHANE	ND	ND	ND	2
1,1,2-TRICHLOROETHANE	ND	ND	ND	1
TRICHLOROETHYLENE	ND	ND	ND	1
TRICHLOROFLUOROMETHANE	ND	ND	ND	2
M+P-XYLENE	TR	ND	ND	2
O-XYLENE	1.5	ND	ND	1
VINYL CHLORIDE	ND	ND	ND	5
OTHER AROMATIC COMPOUNDS	16	ND	ND	1

MDL = METHOD DETECTION LIMITS

ND = NOT DETECTED

TR = TRACE

OTHER AROMATIC COMPOUNDS = Total concentration of tri- and tetramethylbenzenes using the response factor of mesitylene.

CONCENTRATION OF POLYCYCLIC AROMATIC HYDROCARBONS IN WATER

COMPOUND	ug/L		MDL
	W-2087 KMV-002	W-2087 KMV-006*	
NAPHTHALENE	ND	ND	1
ACENAPHTYLENE	ND	ND	1
ACENAPHTHENE	ND	ND	1
FLUORENE	ND	ND	1
PHENANTHRENE	ND	ND	1
ANTHRACENE	ND	ND	1
FLUORANTHRENE	ND	ND	1
PYRENE	ND	ND	1
BENZ(A)ANTHRACENE	ND	ND	1
CHRYSENE	ND	ND	1
BENZO(B)FLUORANTHRENE	ND	ND	1
BENZO(K)FLUORANTHRENE	ND	ND	1
BENZO(A)PYRENE	ND	ND	1
INDENO(1,2,3-CD)PYRENE]			
DIBENZ(A,H)ANTHRACENE]	ND	ND	3
BENZO(G,H,I)PERYLENE	ND	ND	2.5

MDL = METHOD DETECTION LIMIT

ND = Not Detected

Total concentration of indeno(1,2,3-cd)pyrene and dibenz(a,h)anthracene is shown in the row for dibenz(a,h)anthracene.

NO 007517

WHITE - CRA OFFICE COPY  
YELLOW - RECEIVING LABORATORY COPY  
PINK - CRA LABORATORY COPY  
GOLDEN ROD - SHIPPERS

DATE May 31, 1990

CLIENT  
ORDER # 2087

Attention: Mr. G. Chevreau

REPORT # NL-7287

RE: Analysis of Water Samples - Project : 2087

Sir,

Two (2) water samples, received May 4, 1990, were extracted May 10, 1990 and analysed for polycyclic aromatic hydrocarbons by gas chromatography with flame ionization detection (EPA 610). Results are shown in the attached Table.

Chromatograms will be kept on file.

Regards,

NOVALAB LIMITED



B.B. Crowley, B.Sc.



Approved by J.D. Fenwick, Ph.D., P.Chem.

BEC/er  
encl.



CONCENTRATION OF POLYCYCLIC AROMATIC HYDROCARBONS IN WATER  
ug/L


COMPOUND	W-3	W-4	MDL
	03/05/90	03/05/90	
NAPHTHALENE	-	-	1.2
ACENAPHTHYLENE	-	-	1.5
ACENAPHTHENE	-	-	1.2
FLUORENE	-	-	1.5
PHENANTHRENE	-	-	2
ANTHRACENE	-	-	2
FLUORANTHENE	-	-	2
PYRENE	-	-	1.5
BENZ(A)ANTHRACENE	-	-	2
CHRYSENE	-	-	2
BENZO(B,K)FLUORANTHENE	-	-	4
BENZO(A)PYRENE	-	-	3
INDENO(1,2,3-CD)PYRENE}	-	-	8
DIBENZ(A,B)ANTHRACENE}			
BENZO(GHI)PERYLENE	-	-	5

MDL = METHOD DETECTION LIMIT

Total concentration of indeno (1,2,3-CD)pyrene and dibenz(A,B)anthracene is shown in the row of indeno (1,2,3-CD) pyrene.



RIVER E.C.E.  
STATION 10.2  
(APPROXIMATE  
LOCATION)



Drawn By	Scale	Date	Project No.	Sheet No.
Checked By	Field Book	Project No.	Drawing No.	
Approved				
Date	Initial			

FORMER GALT GAS CO. SITE  
CAMBRIDGE, ONTARIO

SITE PLAN

<b>CRA</b> Consulting Engineers <b>CONESTOGA-ROVERS &amp; ASSOCIATES LIMITED</b> 851 Colby Drive Waterloo, Ontario Canada N2V 1C2				
Drawn By	Scale	Date	Project No.	Sheet No.
Checked By	Field Book	Project No.	Drawing No.	
		2087		PLAN 1

LAN

3AS  
011



PROTECTING OUR ENVIRONMENT  
HERITAGE



